

PROVISIONAL BILLS OF QUANTITIES

FOR

REPAIR AND RENOVATIONS AT COLESBERG WEIGHBRIDGE

FOR

Department of Transport, Safety and Liason

ARCHITECTS

Department of Roads and Public Works

9-11 Stockroos Street

Floors

Kimberley

8301

Tel. (053) 839 2100 Fax: (053) 839 2100

e Mail:

Principal Agent

Department of Roads and Public Works

Tel. (053) 839 2100 Fax: (053) 839 2100

e Mail:

QUANTITY SURVEYORS

Department of Roads and Public Works

Quantity Surveyors and Construction Consultants

Tebogo Leon Tume Complex

9-11 Stockroos Street


Squarehill Park

Floors 8301

Tel. (053) 839 2100

Fax: (053) 839 2109

e Mail: dmaqutyana@ncdrpw.com





SECTION NO. 1 PRELIMINARIES AND GENERAL



			Amount	
	SECTION NO. 1			
	PRELIMINARIES AND GENERAL			
	MEANING OF TERMS 'TENDER / TENDERER'			
	Any reference to the words 'Tender' or 'Tenderer' herein and/or in any other documentation shall be construed to have the same meaning as the words 'Bid' or 'Bidder'			
	<u>PRELIMINARIES</u>			
	The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein.			
	The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause.			
	These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable".			
	PRICING OF PRELIMINARIES			
	Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item			
	Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities.			
	SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT			
	A1.0 DEFINITIONS AND INTERPRETATION			
1	Clause 1.0			
	Clause 1.1 Definition of "Commencement Date" is added:			
	"COMMENCEMENT DATE" means the date that the agreement, made in terms of the Form of Offer and Acceptance, comes into effect			
	Clause 1.1 Definition of "Construction Guarantee" is amended by replacing it with the following:			
	"CONSTRUCTION GUARANTEE" means a guarantee at call obtained by the contractor from an institution approved by the employer in terms of the employer's construction guarantee form as selected in the schedule			
	Clause 1.1 Definition of "Construction Period" is amended by replacing it with the following:			
	"CONSTRUCTION PERIOD" means the period commencing on the commencement date and ending on the date of practical completion			
	Clause 1.1 Definition of "Corrupt Practice" is added:			
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries 117			
	117			



			NCDTSL01	/2024
			Amount	
	"CORRUPT PRACTICE" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution.			
	Clause 1.1 Definition of "Fraudulent Practice" is added:			
	"FRAUDULENT PRACTICE" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial non-competitive levels and to deprive the tenderer of the benefits of free and open competition.			
	Clause 1.1 Definition of "Interest" is amended by replacing it with the following:			
	"INTEREST" means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be the rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999)			
	Clause 1.1 Definition of "Principal Agent" is amended by replacing it with the following:			
	"PRINCIPAL AGENT" means the person or entity appointed by the employer and named in the schedule. In the event of a principal agent not being appointed, then all the duties and obligations of a principal agent as detailed in the agreement shall be fulfilled by a representative of the employer as named in the schedule			
	Clause 1.1 Definition of "Security" is amended by replacing it with the following:			
	"SECURITY" means the form of security provided by the employer or contractor, as stated in the schedule, from which the contractor or employer may recover expense or loss			
	Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"			
	Clause 1.6.4 is amended by replacing it with the following:			
	No clause	Item		
	OBJECTIVE AND PREPARATION			
	A2.0 OFFER, ACCEPTANCE AND PERFORMANCE			
2	Clause 2.0	Item		
	A3.0 DOCUMENTS			
3	Clause 3.0			
	Clause 3.2.1 is amended by replacing "14.1" with "14.0"			
	Clause 3.7 is amended by the addition of the following:			
	classes on to amortion by the deathern of the following.			
		_		
	Carried To Section Summary Section No. 1	R		
	Bill No. 1			
	Preliminaries			
	118			



I		1	NCD15L01/	2024
			Amount	
	The contractor shall supply and keep a copy of the JBCC Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the site, to which the employer, principal agent and agents shall have access at all times.			
	Clause 3.10 is amended by replacing the second reference to "principal agent" with the word "employer"	Item		
	A4.0 DESIGN RESPONSIBILITY			
4	Clause 4.0			
	Clause 4.3 is amended by replacing it with the following: No clause.	ltem		
	A5.0 EMPLOYER'S AGENTS			
5	Clause 5.0 Clause 5.1.2 is amended to include clauses 32.6.3, 34.3, 34.4 and 38.5.8	Item		
	A6.0 SITE REPRESENTATIVE			
6	Clause 6.0	Item		
	A7.0 COMPLIANCE WITH REGULATIONS			
7	Clause 7.0			
	Note:			
	A separate clause has been included in Section C:			
	Specific Preliminaries of the bills of quantities / lump sum document for the contractor to have the opportunity to price for all the requirements of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification.	Item		
	, ,	item		
	A8.0 WORKS RISK Clause 8.0	lt a ma		
8		Item		
	A9.0 INDEMNITIES			
9	Clause 9	Item		
	A10.0 WORKS INSURANCES			
10	Clause 10.0			
	Clause 10.0 is amended by the addition of the following clauses:			
	10.5 Damage to the Works			
	(a) Without in any way limiting the contractor's obligations in terms of the contract, the contractor shall bear the full risk of damage to and/or destruction of the works by whatever cause during construction of the works and hereby indemnifies and holds harmless the employer against any such damage. The contractor shall take such precautions and security measures and other steps for the protection and security of the works as the contractor may deem necessary			
	Carried To Section Summary Section No. 1	R		
	Bill No. 1			
	Preliminaries			
	119			



	R & R AT COLESBI	ERG WEIGHBR	IDGE - Principal Cont NCDTSL01/2	
			Amount	
(b) The contractor shall at all times proceed in dispose of any debris arising from damage to to rebuild, restore, replace and/or repair the w	or destruction of the works and			
(c)The employer shall carry the risk of damage and materials paid for by the employer that is as set out in 10.6				
(d) Where the employer bears the risk in term shall, if requested to do so, reinstate any damworks and the costs of such reinstatement shaterms of 32.0 hereof	age or destroyed portions of the			
10.6 Injury to Persons or loss of or damage to	Properties			
(a) The contractor shall be liable for and herely against any liability, loss, claim or proceeding or by statute, consequent upon personal injuring whomsoever arising out of or in the course of the works unless due to any act or negligence actions the employer is legally liable	whether arising in common law es to or the death of any person or caused by the execution of			
(b) The contractor shall be liable for and herek against any liability, loss, claim or proceeding damage to any moveable or immovable or per contiguous to the site, whether belonging to or employer or any other body or person, arising reason of the execution of the works unless drany person for whose actions the employer is	consequent upon loss of or rsonal property or property r under the control of the out of or in the course of or by ue to any act or negligence of			
(c) The contractor shall, upon receiving a cont principal agent, cause the same to be made g workmanlike manner at his own cost and in do be entitled to cause it to be made good and to the contractor or to deduct the same from amount of the contractor.	lood in a perfect and efault thereof the employer shall b recover the cost thereof from			
(d) The contractor shall be responsible for the portions of the premises placed under his con purpose of executing the works until the issue completion	trol by the employer for the			
(e) Where the execution of the works involves interference with support to adjoining propertie or any structures to be altered or added to, the adequate insurance and will remain adequate specific limit stated in the contract against the damage to such property consequent on such the support until such portion of the works has	es including land or structures e contractor shall obtain ly insured or insured to the death of or injury to persons or removal or interference with			
(f) The contractor shall at all times proceed im remove or dispose of any debris and to rebuild such property and to execute the works				
10.7 High risk insurance				
	Carried To Section Summary	R		
Section No. 1				
Bill No. 1				
Preliminaries	120			



		DGE - Principal Contr NCDTSL01/20
		Amount
In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:		
10.7.1 Damage to the works		
The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage to and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above.		
The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary		
When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs		
10.7.2 Injury to persons or loss of or damage to property		
The contractor shall be liable for and hereby indemnifies and holds harmless the employer against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of or caused by a catastrophic ground movement as mentioned above		
The contractor shall be liable for and hereby indemnifies the employer against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site, whether belonging to or under the control of the employer or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract		
10.7.3 It is the responsibility of the contractor to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the contractor's obligations in terms of the contract, the contractor shall, within twenty-one (21) calendar days of the commencement date but before commencement of the works, submit to the employer proof of such insurance policy, if requested to do so		
10.7.4 The employer shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the contractor's default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the contractor or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the employer and the contractor and for this purpose all these contracts shall be considered		
one indivisible whole.	Item	
A11.0 LIABILITY INSURANCES		
Clause 11.0	Item	
Carried To Section Summary	R .	
Section No. 1	`\	
Bill No. 1		
Preliminaries		
121		



		NCDTSL01/	/20
		Amount	
A12.0 EFFECTING INSURANCES			
Clause 12.0	Item		
A13.0 No clause			
A14.0 SECURITY			
14.3.4 On the date of payment of the amount in the final payment certificate, the employer shall refund the remainder of the cash deposit to the contractor.			
14.3.5 The employer shall be entitled to recover the expense and loss from the cash deposit in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the cash deposit security or portions thereof to the contractor.			
14.3.6 The parties expressly agree that neither the employer nor the contractor shall be entitled to cede the rights to the deposit to any third party			
14.4 Where security as variables construction guarantee of ten per cent (10%) of the contract sum (excluding VAT) has been selected:			
14.4.1 The contractor shall furnish the employer with an acceptable variable construction guarantee equal to ten per cent (10%) of the contract sum (excluding VAT) within twenty-one (21) calender days from commencement day			
14.4.2 The variable construction guarantee shall reduce and expire in terms of the Variable Construction Guarantee form included in the invitation to tender			
14.4.3 The employer shall return the variable construction guarantee to the contractor within fourteen (14) calender days of it expiring			
14.4.4 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer shall issue a written demand in terms of the variable construction guarantee			
14.5 Where security as fixed construction guarantee of five per cent (5%) of the contract sum (excluding VAT) and five per cent (5%) payment reduction of the value certified in the payment certificate (excluding VAT) has been selected:			
14.5.1 The contractor shall furnish a fixed construction guarantee to the employer equal in value to five per cent (5%) of the contract sum (excluding VAT)			
14.5.2 The fixed construction guarantee shall come into force on the date of issue and shall expire on the date of the last certificate of practical			
14.5.3 The employer shall return the fixed construction guarantee to the contractor within fourteen (14) calender daysof it expiring			
14.5.4 The payment reduction of the value certified in the payment certificate shall be in terms pf 31.8 (A) and 34.8			
14.5.5 Where the employer has the right of recovery against the contractor in terms of 33.0, the employer shall be entitled to issue a written demand in terms of the construction guarantee or may recover from the payment reduction or may be both			
Carried To Section Summary	r R		T
Section No. 1			+
Bill No. 1			
Preliminaries			
122			



			NCDTSL01/	2024
			Amount	
	14.6 Where security as cash deposit of five per cent (5%) of the contract sum (excluding VAT) and payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT) has been selected:			
	14.6.1 The contractor shall furnish the employer with a cash deposit equal in value to five per cent (5%) of the contract sum (excluding VAT) within twentty-one (21) calender days from commmencement date			
	14.6.2 Within twenty-one (21) calender days of the date of practical completion of the works the employer shall refund the cash deposit in total to the contractor			
	14.6.3 The payment reduction of value certified in a payment certificate shall be mutatis mutandi in terms of 31.8(A)			
	14.6.4 Where the employer has the right of recovery against the contractor in terms of 33.0 the employer may issue a written demand in terms of 33.4 or may recover from the payment reduction or may be both			
	14.7 Where security as payment reduction of ten per cent (10%) of the value certified in payment certificate (excluding VAT) has been selected:			
	14.7.1 The payment reduction of the value certified in a payment certificate shall be mutatis mutandi in terms of 31.8(B)			
	14.7.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provision of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction or portions therof to the contractor			
	14.8 Payments made by the guarantor to the employer in terms of the fixed or variable construction guarantee shall not prejudice the rights of the employer or contractor in terms of this agreement			
	14.9 Should the contractor fail to furnish the security in terms of 14.2, the emplyer in his sole discretion and without notification to the contractor, is entitled to change the contractor's selected form of security to that of a ten per cent (10%) payment reduction of the value certified in the payment certificate (excluding VAT) whereafter 14.7 shall be applicable	Item		
13	Clause 14.0			
	Causes 14.1 - 14.8 are amended by replacing them with the following:			
	14.1 In respect of contracts with a contract sum up to R1 million the security to be provided by the contractor to the employer will be a payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT)			
	14.1.1 The payment reduction of the value certified in the payment certificate shall be mutatis mutandi in terms of 31.8(A)			
	14.1.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor			
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries			
	123			



Amount 14.2 In respect of contractors with a contract sum above R1 million, the contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6 or 14.7 as stated in the schedule. Such security shall be provided to the employer within twenty-one (21) calender days from the commencement date. Should the contractor fail to provide the employer with the selected security with newnty-one (21) calender days from commencement date, the security in terms of 14.7 shall be deemed to have been selected 14.3. Where security as a cash deposit of ten per cent (10%) of the contract sum, (excluding VAT) has been selected: 14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of contract sum (excluding VAT) within twenty-one (21) calender days form commencement date. 14.3.2 Whithin twenty-one (21) calender days of the date of practical completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Whithin twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor 24.3 Subtlim twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor 25.2 Clause 15.1 is amended by replacing it with: 26.2 Clause 15.1 is amended by the addition of the following clause: 27.3 Clause 15.1 is amended by the addition of the following clause: 28.4 Clause 15.2 is amended by the addition of the following clause: 28.5 Clause 15.2 is amended by the addition of the following clause: 28.6 Clause 15.2 is amended by the addition of the following clause: 28.6 Clause 16.0 28.7 Claus		Kakin oolessi	LIKO WEIGHBIK	NCDTSL01/	
contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6 or 14.7 as stated in the schedule. Such security shall be provided to the employer within twenty-one (21) calender days from the commencement date. Should the contractor fail to provide the employer with the selected security within twenty-one (21) calender days from commencement date, the security in terms of 14.7 shall be deemed to have been selected 14.3 Where security as a cash deposit of ten per cent (10%) of the contract sum. (excluding VAT) has been selected: 14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of contract sum (excluding VAT) within twenty-one (21) calender days from commencement date. 14.3.2 Within twenty-one (21) calender days of the date of practical completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (13%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (15%) of the contract value (excluding VAT) and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (15%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION 21. Calcause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act. 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.0 Is amended by replacing it with the following clause: 15.1 Clause 17.0 Clause 17.0 Clause 17.1 It is amended by deleting the words "and				Amount	
contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6 or 14.7 as stated in the schedule. Such security shall be provided to the employer within twenty-one (21) calender days from the commencement date. Should the contractor fail to provide the employer with the selected security within twenty-one (21) calender days from commencement date, the security in terms of 14.7 shall be deemed to have been selected 14.3 Where security as a cash deposit of ten per cent (10%) of the contract sum. (excluding VAT) has been selected: 14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of contract sum (excluding VAT) within twenty-one (21) calender days from commencement date. 14.3.2 Within twenty-one (21) calender days of the date of practical completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (13%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (15%) of the contract value (excluding VAT) and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (15%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION 21. Calcause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act. 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.0 Is amended by replacing it with the following clause: 15.1 Clause 17.0 Clause 17.0 Clause 17.1 It is amended by deleting the words "and					
sum. (excluding VAT) has been selected: 14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of contract sum (excluding VAT) within twenty-one (21) calender days from commencement date. 14.3.2 Within twenty-one (21) calender days of the date of practical completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1.3 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 17.0 Clause 17.0 Clause 17.1.11 is amended by deleting the words *and the appointment of nominated and selected subcontractors* Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6 or 14.7 as stated in the schedule. Such security shall be provided to the employer within twenty-one (21) calender days from the commencement date. Should the contractor fail to select the security to be provided or should the contractor fail to provide the employer with the selected security within twenty-one (21) calender days from commencement			
value to ten per cent (10%) of contract sum (excluding VAT) within twenty-one (21) calender days from commencement date. 14.3.2 Within twenty-one (21) calender days of the date of practical completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS 14. Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1.3 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor complying with the terms of 15.1.4 Litem A16.0 ACCESS TO THE WORKS 15. Clause 16.0 Litem A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		14.3 Where security as a cash deposit of ten per cent (10%) of the contract sum. (excluding VAT) has been selected:			
completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor 14.3.3 Within twenty-one (21) calender days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS 14 Clause 15.1.1 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1.2 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS 15 Clause 16.0 Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" R Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		value to ten per cent (10%) of contract sum (excluding VAT) within twenty-			
the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor EXECUTION A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS 14. Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS 15. Clause 16.0 Clause 17.0 Clause 17.1.1 is amended by deleting the words "and the appointment of nominated and selected subcontractors" R Carried To Section Summary Section No. 1 Bill No. 1 Prelliminaries		completion of works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and			
A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS Clause 15.0 Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" R Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the			
Clause 15.0 Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" R Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		EXECUTION			
Clause 15.1.1 is amended by replacing it with: No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 Item A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS			
No clause Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 ### A16.0 ACCESS TO THE WORKS Clause 16.0 ### Litem A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary R	14	Clause 15.0			
Clause 15.1.2 is amended by replacing it with: The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		Clause 15.1.1 is amended by replacing it with:			
The security selected in terms of 14.0 Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 Item A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Item Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		No clause			
Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		Clause 15.1.2 is amended by replacing it with:			
15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Item Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		The security selected in terms of 14.0			
Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date Clause 15.2.1 is amended by replacing it with the following clause: Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Item Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		Clause 15.1 is amended by the addition of the following clause:			
contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4 Item A16.0 ACCESS TO THE WORKS Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.0. Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one			
Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Item Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		contractor possession of the site within ten (10) working days of the	Item		
Clause 16.0 Item A17.0 CONTRACT INSTRUCTIONS Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Item Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		A16.0 ACCESS TO THE WORKS			
Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries	15		Item		
Clause 17.0 Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		A17.0 CONTRACT INSTRUCTIONS			
Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries	16				
nominated and selected subcontractors" Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		Clause 17.1.11 is amended by deleting the words "and the appointment of			
Section No. 1 Bill No. 1 Preliminaries			Item		
Section No. 1 Bill No. 1 Preliminaries					
Section No. 1 Bill No. 1 Preliminaries		Carried To Soction Summan	.		
Bill No. 1 Preliminaries		1	R		
Preliminaries					
124		Preliminaries			
		124			



			Amount	
	A49 0 SETTING OUT OF THE WORKS			
17	A18.0 SETTING OUT OF THE WORKS Clause 18.0	Item		
	A19.0 ASSIGNMENT	11.0111		
18	Clause 19.0	Item		
	A20.0 NOMINATED SUBCONTRACTORS			
19	Clause 20.0			
	Clause 20.1.3 is amended by replacing it with the following:			
	No clause			
	Note:			
	See item B9.1 hereinafter for adjustment of attendance on nominated subcontractors executing work allowed for under provisional sums	Item		
	A21.0 SELECTED SUBCONTRACTORS			
20	Clause 21.0 Clause 21 is amended by replacing it with:			
	No clause	Item		
	A22.0 EMPLOYER'S DIRECT CONTRACTORS			
21	Clause 22.0	Item		
	A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS			
22	Clause 23.0	Item		
	COMPLETION			
	A24.0 PRACTICAL COMPLETION			
23	Clause 24.0	Item		
	A25.0 WORKS COMPLETION			
24	Clause 25.0	Item		
	A26.0 FINAL COMPLETION			
25	Clause 26.0			
	Clause 26.1.2 is amended by inserting "#" next to 26.1.2	Item		
	A27.0 LATENT DEFECTS LIABILITY PERIOD			
26	Clause 27.0	Item		
	A28.0 SECTIONAL COMPLETION			
27	Clause 28.0	Item		
	A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION			
28	Clause 29.0			
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1 Preliminaries			
	125			



			NCDTSL01	/2024
			Amount	
	Clause 29.2.5 is amended by replacing it with:	lt a ma		
	No clause	Item		
	A30.0 PENALTY FOR NON-COMPLETION			
29	Clause 30.0	Item		
	PAYMENT			
	A31.0 INTERIM PAYMENT TO THE CONTRACTOR			
30	Clause 31.0			
	Clause 31.5.2 is amended by replacing "14.7.1" with "14.0"			
	Clause 31.8 is amended by replacing it with the following two alternative clauses:			
	Alternative A			
	31.8(A) Where a security is selected in terms of 14.1; 14.5 or 14.6, the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full.			
	The value certified shall be subject to the following percentage adjustments:			
	31.8(A).1 Ninety-five per cent (95%) of such value in interim payment certificates issued up to the date of practical completion			
	31.8(A).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion			
	31.8(A).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6			
	31.8(A).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer.			
	In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate Alternative B			
	31.8(B) Where security as a payment reduction in terms of 14.7 has been selected, the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full.			
	The value certified shall be subject to the following percentage adjustments			
	31.8(B).1 Ninety per cent (90%) of such value in interim payment certificates issued up to the date of practical completion			
	31.8(B).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion			
	31.8(B).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6			
	Carried To Section Summary	R		
	Section No. 1	· · ·		
	Bill No. 1			
	Preliminaries			
	126			



31.8(B).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer. In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate Clause 31.12 is amended by deleting the following: Payment shall be subject to the employer giving the contractor a tax invoice for the amount due A32.0 ADJUSTMENT TO THE CONTRACT VALUE Clauses 32.0.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: 'due to no fault of the contractor' tlem A33.0 RECOVERY OF EXPENSE AND LOSS Clause 33.0 Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.3 is amended by removing "#" next to 34.2 Clause 34.3 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days' with "venty-one (21) calendar days' and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1 4 estate being sequestrated, liquidated or surendered in terms of the insolvency laws in force within the Republic of South Africa 36.1 5 in the judgment of the employer, has engaged in currup of refaudiuent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries				Amount	2024
certificate in terms of 34.6 except where the amount certified is in favour of the employer. In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate Clause 31.12 is amended by deleting the following: Payment shall be subject to the employer giving the contractor a tax invoice for the amount due A32.0 ADJUSTMENT TO THE CONTRACT VALUE Clauses 32.0 Clauses 32.51, 13.2.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" Item A33.0 RECOVERY OF EXPENSE AND LOSS Clauses 33.0 Clauses 34.0 Clauses 34.1 is amended by removing "#" next to 34.1 Clauses 34.2 is amended by removing "#" next to 34.2 Clauses 34.3 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.7.1" Clauses 34.1 is amended by replacing "seven (7) calendar days" with "werehy-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Cancellation A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clauses 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by the addition of the following clause: Clause 36.3 is amended by the addition of the following clause:				Amount	
applicable to the final payment certificate Clause 31.12 is amended by deleting the following: Payment shall be subject to the employer giving the contractor a tax invoice for the amount due A32.0 ADJUSTMENT TO THE CONTRACT VALUE 31 Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" A33.0 RECOVERY OF EXPENSE AND LOSS 32 Clauses 33.0 Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.1 is amended by removing "#" next to 34.2 Clause 34.2 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.7.1" Clause 34.3 is amended by replacing "seven (7) calendar days" with "wenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 setate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		certificate in terms of 34.6 except where the amount certified is in favour of			
Payment shall be subject to the employer giving the contractor a tax invoice for the amount due A32.0 ADJUSTMENT TO THE CONTRACT VALUE Clause 32.0 Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" Item A33.0 RECOVERY OF EXPENSE AND LOSS Clause 33.0 Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.1 is amended by removing "#" next to 34.2 Clause 34.3 is amended by removing "#" next to 34.2 Clause 34.3 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries					
for the amount due A32.0 ADJUSTMENT TO THE CONTRACT VALUE Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" Item A33.0 RECOVERY OF EXPENSE AND LOSS 2 Clause 33.0 Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		Clause 31.12 is amended by deleting the following:			
Clause 32.0 Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" Item			ltem		
Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: "due to no fault of the contractor" A33.0 RECOVERY OF EXPENSE AND LOSS Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by removing "#" next to 34.2 Clause 34.3 is amended by removing "#" next to 34.2 Clause 34.3 is amended by replacing the words "where security as a fixed construction guarantee in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1 4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:		A32.0 ADJUSTMENT TO THE CONTRACT VALUE			
following at the end of the sentence: "due to no fault of the contractor" Item A33.0 RECOVERY OF EXPENSE AND LOSS 2 Clause 33.0 Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT 3 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES 34 Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries	31	Clause 32.0			
A33.0 RECOVERY OF EXPENSE AND LOSS Clause 33.0 Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES 34 Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries					
Clause 33.0 Item A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.0 Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by the addition of the following clause: Clause 36.3 is amended by the addition of the following clause: Clause 36.0 is amended by the addition of the following clause: Clause 36.0 is amended by the addition of the following clause:		"due to no fault of the contractor"	Item		
A34.0 FINAL ACCOUNT AND FINAL PAYMENT Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Cancellation A36.0 Cancellation A36.0 Cancellation By EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		A33.0 RECOVERY OF EXPENSE AND LOSS			
Clause 34.0 Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:	32	Clause 33.0	Item		
Clause 34.1 is amended by removing "#" next to 34.1 Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		A34.0 FINAL ACCOUNT AND FINAL PAYMENT			
Clause 34.2 is amended by removing "#" next to 34.2 Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:	33	Clause 34.0			
Clause 34.8 is amended by deleting the words "where security as a fixed construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:		Clause 34.1 is amended by removing "#" next to 34.1			
construction guarantee in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1" Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" Item A35.0 PAYMENT TO OTHER PARTIES Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		Clause 34.2 is amended by removing "#" next to 34.2			
"twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" A35.0 PAYMENT TO OTHER PARTIES 34 Clause 35.0 Item CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries		construction guarantee in terms of 14.4 has been selected or where payment			
Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:		"twenty-one (21) calendar days" and deleting the words "subject to the	Item		
Clause 35.0 CANCELLATION A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:		A35.0 PAYMENT TO OTHER PARTIES			
A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries	34		Item		
Clause 36.1 is amended by the addition of the following clauses: 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause:		CANCELLATION			
36.1.3 refuses or neglects to comply strictly with any of the conditions of contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT			
contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices in competing for or in executing the contract Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		Clause 36.1 is amended by the addition of the following clauses:			
replacing the words "principal agent" with "employer" Clause 36.0 is amended by the addition of the following clause: Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries		contract 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa 36.1.5 in the judgment of the employer, has engaged in corrupt or fraudulent practices			
Carried To Section Summary R Section No. 1 Bill No. 1 Preliminaries					
Section No. 1 Bill No. 1 Preliminaries		Clause 36.0 is amended by the addition of the following clause:			
Section No. 1 Bill No. 1 Preliminaries					
Section No. 1 Bill No. 1 Preliminaries		Carried To Section Summary	R		
Preliminaries		1	IX		
		Bill No. 1			
127					
		127			



			NCDTSL01/2	2024
			Amount	
35	36.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site. The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever Clause 36.0 A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE Clause 37.0	ltem		
	Clause 37.3.5 is amended by replacing "ninety (90)" with "one-hundred and twenty (120)"			
	Clause 37.0 is amended by the addition of the following clause:			
	37.5 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site.			
	The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever	Item		
	A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT			
37	Clause 38.0			
	Clause 38.5.4 is amended by replacing "ninety (90)" with "one-hundred and twenty (120)"			
	Clause 38.0 is amended by the addition of the following clause:			
	38.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site.			
	The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever	Item		
	A39.0 CANCELLATION - CESSATION OF THE WORKS			
38	Clause 39.0			
	Clause 39.3.5 is amended by the addition of the following at the end of the sentence: "within one hundred and twenty (120) working days of completion of such a report"	Item		
	DISPUTE			
	A40.0 DISPUTE SETTLEMENT			
39	Clause 40.0			
	Carried To Section Summary Section No. 1 Bill No. 1 Preliminaries	R		
	128			



1		1	NCD15L01/	202 4
			Amount	
	Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"			
	Clause 40.6 is amended by removing the reference to:			
	No clause			
	Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:			
	Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the mediator and related costs	Item		
	SUBSTITUTE PROVISIONS			
	A41.0 STATE CLAUSES			
40	Clause 41.0	Item		
	CONTRACT VARIABLES			
	A42.0 THE SCHEDULE (DPW-04EC)			
41	Clause 42.0			
	Tenderers are referred to the Contract Data DPW-04(EC) for variables pertaining to this contract	Item		
	SECTION B: JBCC PRELIMINARIES			
	B1.0 DEFINITIONS AND INTERPRETATION			
42	B1.1 Definitions and interpretation			
	See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section.	Item		
	B2.0 DOCUMENTS			
43	B2.1 Checking of documents	Item		
44	B2.2 Provisional bills of quantities	Item		
45	B2.3 Availability of construction documentation	Item		
46	B2.4 Interests of agents	Item		
47	B2.5 Priced documents	Item		
48	B2.6 Tender submission			
	Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"	Item		
	B3.0 THE SITE			
49	B3.1 Defined works area	Item		
50	B3.2 Geotechnical investigation	Item		
51	B3.3 Inspection of the site	Item		
	20.05500010 00	110111		
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries			
	129			



		1		NCDTSL01/	2024
				Amount	
52	B3.4 Existing premises occupied		Item		
53	B3.5 Previous work - dimensional accuracy		Item		
54	B3.6 Previous work - defects		Item		
55	B3.7 Services - known		Item		
56	B3.8 Services - unknown		Item		
57	B3.9 Protection of trees		Item		
58	B3.10 Articles of value		Item		
59	B3.11 Inspection of adjoining properties		Item		
	B4.0 MANAGEMENT OF CONTRACT				
60	B4.1 Management of works		Item		
61	B4.2 Programme for the works		Item		
62	B4.3 Progress meetings		Item		
63	B4.4 Techanical meetings		Item		
64	B4.5 Labour and plant records		Item		
	B5.0 SAMPLES, SHOP DRAWINGS AND MANUF	ACTURERS'			
65	B5.1 Samples of materials		Item		
66	B5.2 Workmanship samples		Item		
67	B5.3 Shop drawings		Item		
68	B5.4 Compliance with manufacturers' instructions		Item		
	TEMPORARY WORKS AND PLANT				
69	B6.1 Deposits and fees		Item		
70	B6.2 Encloser of the works		Item		
71	B6.3 Advertising		Item		
72	B6.4 Plant, equipment, sheds and offices		Item		
73	B6.5 Main notice board		Item		
74	B6.6 Subcontractors' notice board		Item		
	B7.0 TEMPORARY SERVICES				
75	B7.1 Location		Item		
76	B7.2 Water		Item		
	Ca	rried To Section Summary	R		
	Section No. 1		IX		
	Bill No. 1				
	Preliminaries 13)			
ı		I	II		1



	R & R AT COLESBERG WEIGHBRIDGE - Principal Contract NCDTSL01/2024		
			Amount
77	B7.3 Electricity	Item	
78	B7.4 Telecommunication facilities	Item	
79	B7.5 Ablution facilities	Item	
	PRIME COST AMOUNTS		
80	B8.1 Responsibility for prime cost amounts	Item	
	B9.0 ATTENDANCE ON N/S SUBCONTRACTORS		
81	B9.1 General Attendance	Item	
82	B9.2 Special Attendance	Item	
83	B9.3 Commissioning - fuel, water and electricity	Item	
	B10.0 FINANCIAL ASPECTS		
84	B10.1 Statutory taxes, duties and levies	Item	
85	B10.3 Adjustment of preliminaries		
	Clauses B10.3.1 and B10.3.2 are amended by replacing "with working days of taking possession of the site" with "when sub priced bills of quantities / lump sum document"		
86	B10.4 Payment certificate cash flow	Item	
	B11.0 GENERAL		
87	B11.1 Protection of the works	Item	
88	B11.2 Protection/isolation of existing/sectionally occupied wor	ks Item	
89	B11.3 Security of the works	Item	
90	B11.4 Notice before covering work	Item	
91	B11.5 Disturbance	Item	
92	B11.6 Environmental disturbance	Item	
93	B11.7 Works cleaning and clearing	Item	
94	B11.8 Vermin	Item	
95	B11.9 Overhand work	Item	
96	B11.11 As built information	Item	
97	B11.12 Tenant installations	Item	
	Carried To Some Section No. 1 Bill No. 1 Preliminaries	ection Summary R	
	131		



			Amount	
	B1.0 DEFINITIONS AND INTERPRETATION			
	SCHEDULE OF VARIABLES			
	Schedule of variables:			
98	This schedule contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender categorymust be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these Preliminaries Spaces requiring information must be filled in, shown as "not allpicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the schedule. Key cross reference clauses are italicised in [] brackets	ltem		
	12.1 PRE-TENDER INFORMATION			
	12.1.1 Provisional bills of quantities			
	[2.2] The quantities are provisional (Yes/No) = Yes			
	12.1.2 Availability of construction documentation			
	[2.3] Construction documentation is not complete (Yes/No) = Yes			
	12.1.3 Interests of agents			
	[2.4] Details:			
	12.1.4 Defined works area			
	[3.1] Details:			
	12.1.5 Geotechnical investigation			
	[3.2] Details = There is no investigation attached nor carried out on site			
	12.1.6 Existing premises occupied			
	[3.4] Specific requirements:			
	12.1.7 Previous work - dimensional accuracy			
	[3.5] Details:			
	The contractor is responsible fo the accuracy and in the event that existing work done prior the site possession is in accurate, the contractor is to inform the principal agent inmmediately			
	12.1.8 Previous work - defects			
	[3.6] Details:			
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries			
	132			



NCDTSL01/2024 Amount 12.1.9 Services - known [3.7] Details: 12.1.10 Protection of trees [3.9] Specific requirements: The contractor is to preserve all trees on site and is to request instruction from the Principal Agent where trees are constricting the work areas or progress of work. 12.1.11 Inspection of adjoining properties [3.11] Specific requirements: The contractor is to ensure that no harm comes to adjoining buildings or property during the progress of the works. 12.1.12 Enclosure of the works [6.2] Specific requirements: The contractor is to enclose the works in the manner necessary to prevent members of the public, the client's workers or any other persons from being hurt due to coming into areas where construction activities are under way. 12.1.13 Offices [6.4.3] Specific requirements: The contractor shall provide, maintain and remove on completion of the works an office for the exclusive use of the principal agent, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times. **Defined works area** 12.1.14 Main notice board [6.5] Specific requirements: The contractor shall provide, erect where directed, maintain and remove on completion of the works a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering 12.1.15 Subcontractors' notice board [6.6] A Notice Board is required (Yes/No) = No No Specific requirements: Not Applicable 12.1.16 Water [7.2] Carried To Section Summary R Section No. 1 Bill No. 1 **Preliminaries** 133



		Amount	
Option A - by Contractor = Option A Applicable			
Option B - by employer (free of charge)			
Option C - by employer (metered)			
12.1.17 Electricity [7.3]			
Option A - by Contractor = Option A Applicable			
Option B - by employer = (free of charge)			
Option C - by employer = (metered)			
12.1.18 Telecommunications			
[]7.4] Telephone (Yes/No) = Yes			
Facsimile (Yes/No) = No			
12.1.19 Ablution facilities			
[7.5] Option A (by contractor) (Yes/No) = Option A Applicable			
Option B (by employer) (Yes/No) = No			
12.1.20 Protection of existing/sectionally occupied works			
[11.2] Protection is required (Yes/No) = Yes			
12.1.21 Special attendance			
[9.2] Subcontractor (1) details = Not applicable			
12.1.22 Protection of the works			
[11.1] Specific requirements:			
All precautions are to be taken to prevent damage or harm to the works. The client is to be indemnified against any and all eventualities. The existing buildings are to be insured against damage by the employer. However the contractor is to take all necessary precautions to prevent damage to existing buildings and property whilst he is in possession of the site.			
12.1.23 Disturbance			
[11.5] Specific requirements:			
The contractor shall keep the site, structures, etc. well watered during operations to prevent dust and shall provide and erect and remove on completion of the works all necessary temporary dust screens all to the satisfaction of the principal agent			
12.1.24 Environmental disturbance			
[11.6] Specific requirements:			
The contractor is to ensure that no environmental damage occurs on or over the site during the execution of the works and whilst he is in possession of the site. All precautions are to be taken to ensure that the water, soil, vegetation and air on and over the site are not contaminated whilst the contractor is in possession of the site.			
12.2 POST-TENDER INFORMATION			
12.2.1 Payment of preliminaries			
Carried To Section Summary Section No. 1	R		
Bill No. 1			
Preliminaries			
134			



1			NCD I SLU1/.	2024
			Amount	
	[10.2] Option A (prorated) (Yes/No) = Yes			
	Option B (calculated) (Yes/No)			
	12.2.2 Adjustment of preliminaries			
	[10.3] Option A (three categories) (Yes/No) = Yes			
	Option B (detailed breakdown) (Yes/No)			
	12.2.3 Additional agreed preliminaries items			
	Details:			
	Details.			
	SECTION C: SPECIFIC PRELIMINARIES			
	Section C: Specific Preliminaries:			
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item			
	C1 CONTRACT DRAWINGS			
99	* The drawings issued with the tender documents do not comprise the			
	complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself			
	with the nature and extent of the works and the manner in which they are to			
	be executed Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in			
	writing from the principal agent.	Item		
	C2 GENERAL PREAMBLES			
100	The document "Specification of Materials and Methods to be used (PW371-			
	A) and (PW371-B)" is obtainable on the Department's website http://www.publicworks.gov.za/PDFs/consultants_docs/2013/2/PW371-A%			
	20General%20Specification%20edition%202.0_July_2013.pdf and			
	http://www.publicworks.gov.za/PDFs/consultants_docs/2013/2/PW371-B% 20Particular%20Specification%20edition%202.0%20July2013.docx_under			
	"Consultants Guidelines), and shall be read in conjunction with the bills of			
	quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used	lt a .aa		
		Item		
	C3 TRADE NAMES			
101	Wherever a trade name for any product has been described in the bills of quantities / lump sum document, the tenderer's attention is drawn to the fact			
	that any other product of equal quality may be used subject to the written			
	approval of the principal agent being obtained prior to the closing date for submission of tenders If prior written approval for an alternative product is			
	not obtained, the product described shall be deemed to have been tendered			
	for	Item		
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries 125			
	135			



			NCDTSL01/	2024
			Amount	
	C4 IMPORTED MATERIALS AND EQUIPMENT			
102	Where imported items are listed in the tender documents, the tenderer shall provide all the information called for, failing which the price of any such item, materials or equipment shall be excluded from currency fluctuations. (refer to Schedule of Imported Materials and Equipment DPW-23(EC) to be completed by tenderer) Notwithstanding any provisions elsewhere regarding the adjustment of contract prices, the price of any item, material or equipment listed in terms of this clause shall be excluded from the Contract Price Adjustment Provisions (if applicable)	ltem		
	C5 VIEWING THE SITE IN SECURITY AREAS			
103	The site is situated in a security area and the tenderer must arrange with the unit commander or other responsible officer to obtain permission to enter the site for tendering purposes	ltem		
	C6 COMMENCEMENT OF WORKS IN SECURITY AREAS			
104	As the works falls within a security area the contractor must give the unit commander or other responsible officer notice before commencement of the works. Should the contractor fail to make such arrangements, admission to the site may be refused and any additional costs will be for the contractor's account	ltem		
	C7 ENTRANCE PERMITS TO SECURITY AREAS			
105	As the works falls within a security area the contractor shall obtain entrance permits for his personnel and workmen entering the area and shall comply with all regulations and instructions which may be issued from time to time regarding the protection of persons and property under the control of the Defence Force, Police or chief security officer	ltem		
	C8 SECURITY CHECK OF PERSONNEL			
	Details:			
106	The principal agent may require the contractor to have his personnel and workmen, or a certain number of them, security classified — In the event of the principal agent requesting the removal of a person or persons from the works for security reasons, the contractor shall do so forthwith and shall thereafter ensure that such person or persons are denied access to the works and the site and/or to any document or information relating to the works	ltem		
	C9 PROHIBITION ON TAKING OF PHOTOGRAPHS			
107	In terms of article 119 of the Defence Act, 44 of 1957, it is prohibited to sketch or to take photographs of any military site or installation or any building or civil works thereon or to be in possession of a camera or other apparatus used for taking of photographs except when authorized thereto by or on behalf of the Minister			
	The same prohibition is also applicable to all correctional institutions in terms of article 44.1(e) of the Correctional Services Act 8 of 1959	ltem		
	Section No. 1 Bill No. 1 Proliminarias	R		
	Preliminaries 136			



		11	NCDTSL01/	2024
			Amount	
	C10 HIV/AIDS AWARENESS			
	It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.			
	Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained			
	The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance.			
	The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment			
	C10.1 AWARENESS CHAMPION			
108	Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification	Item		
	C10.2 AWARENESS WORKSHOPS			
109	Selection and appointment of a competent Service Provider approved by the principal agent, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi-media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification	ltem		
	C10.3 POSTERS, BOOKLETS, VIDEOS, ETC.			
110	Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the construction period, all in accordance with the HIV/AIDS			
	Specification	Item		
	C10.4 ACCESS TO CONDOMS			
111	Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the construction period, all in accordance with the HIV/AIDS Specification	ltem		
	Carried To Section Summary	R		
	Section No. 1 Bill No. 1			
	Preliminaries			
	137			



			NCDTSL01/	2024
			Amount	
	C10.5 MONITORING			
112	Monitoring HIV/AIDS awareness of workers, providing the principal agent with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the construction period and close out, all in accordance with the HIV/AIDS Specification	Item		
	C11 OCCUPATIONAL HEALTH AND SAFETY ACT			
113	The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993).			
	It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.			
	The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance.			
	The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.			
	Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained.	Item		
114	The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993).			
	It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.			
	The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance.			
	The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.			
	Carried To Section Summary	R -		
	Section No. 1			
	Bill No. 1			
	Preliminaries 138			
	100	II		l



			NCDTSL01	/2024
			Amount	
	Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained. Refer to the attached specification at the back of these bills of quantities EPWP	ltem		
	Expanded Public works programme:			
115	The contractor is to keep records of labour in terms of labour employed and submit labour records from a reliable payroll system that corresponds with the South African law governing labour records.	ltem		
116	EPWP fourtnightly reporting:			
	The Tenderer is to submit a monthly report on the template available from the Principal Agent at the site handover, which requires labour amounts spent and reported dermographically, geographically and also values spent on EPWP labour.	ltem		
	CARTING OF WATER FOR CONSTRUCTION			
	Carting of water on site			
117	The contractor is to make provision to cart water onto site as there maybe no suffitient water available on site.	Item		
	PORTFOLIO OF EVIDENCE			
	GPS Tagged photos:			
118	The contractor shall use a camera with a function that adds GPS co- ordicates to the saved photos under the properties of the photo.			
	If the photos are not showing the GPS co-ordinates matching those of the site address of this bid, then the photos cannot be used as evidence.	Item		
	Proof of Depths of foundation excavations:			
119	The contractor is to take and email to the Quantity Surveyor, GPS tagged photos of the:			
	a) Excavation depths vs natural ground/ reduced level			
	b) Top of footing vs natural ground/ reduced level			
	c) Top of Surface bed vs natural ground/ reduced level			
	Note:			
	The above is to be taken at all external corners of the building, by means of a surveying staff.	Item		
	Carried To Section Summary	R		
	Section No. 1			
	Bill No. 1			
	Preliminaries 139			
	139			



			Amount	
120	ELECTRICAL INSTALLATION & OTHER SUBCONTRACTOR'S PRELIMINARIES Selected/Nominated/Domestic Subcontractors preliminaries and other indirect costs are to be priced herein under as there will be no compensation for extra preliminaries for the contractors subcontractors: Fixed, Value and time related items	ltem		
120	rixed, value and time related items	nem		
	Carried To Section Summary Section No. 1	R		
	Bill No. 1 Preliminaries			
	140			



	R & R AT COLESB	ERG WEIGHBR	IDGE - Principal Contract NCDTSL01/2024
			Amount
SECTION NO. 1			
PRELIMINARIES AND GENERAL			
SECTION SUMMARY			
		Page	
	Brought forward from page	117	
	Brought forward from page	118	
	Brought forward from page	119	
	Brought forward from page	120	
	Brought forward from page	121	
	Brought forward from page	122	
	Brought forward from page	123	
	Brought forward from page	124	
	Brought forward from page	125	
	Brought forward from page	126	
	Brought forward from page	127	
	Brought forward from page	128	
	Brought forward from page	129	
	Brought forward from page	130	
	Brought forward from page	131	
	Brought forward from page	132	
	Brought forward from page	133	
	Brought forward from page	134	
	Brought forward from page	135	
	Brought forward from page	136	
	Brought forward from page	137	
	Brought forward from page	138	
	Brought forward from page	139	
	Brought forward from page	140	
Section No. 1	Carried to Next	R	
SECTION SUMMARY			
	141		
	'	'	ı



Brought from Previous R

SECTION NO. 2 BUILDING WORKS



1		1		NCDTSL01/2
	Unit	Quantity	Rate	Amount
SECTION NO. 2				
BUILDING WORKS				
BILL NO. 1				
ALTERATIONS [PROVISIONAL]				
SUPPLEMENTARY PREAMBLES				
Descriptions and preambles				
The full descriptions of the items and all preambles in other trades, shall, unless otherwise stated, be applicable to the relevant items in this trade.				
General In the taking down and removal of existing work, the utmost care is to be observed to avoid any structural or other damage to the remaining portion of the building.				
The contractor must provide for all strutting, shoring, supporting, etc., to stabilise the existing structure when alterations are in process.				
The utmost care is to be observed when existing electrical installation, electronic installation, water pipes, telephone and other services are encountered during the alterations and tampering with this services will not be allowed.				
The Representative/Agent must be given notice where disconnections or alterations to existing services are to be encountered.				
The contractor must prevent any nuisance from dust when work is in process.				
Repairing of existing work				
The contractor must allow for making good in all trades to existing work where damaged or disturbed by any alterations and/or removal of existing fixed and/or non-fixed structures with all necessary new materials to match existing and leave complete and perfect in every respect.				
Form new openings or alter existing openings				
Unless otherwise described, the wording "Form new openings" or "Alter existing openings" shall be deemed to include the breaking out of existing brickwork or blockwork, building up of new brickwork or blockwork, casting of new in-situ concrete, prestressed precast concrete lintels, formwork, strutting, etc., the building up of reveals or portions of the opening as described with brickwork or blockwork, toothing and bonding to existing work and making good of existing surfaces on both sides and reveals as described.				
Carried to Collection Section No. 2 Bill No. 1			R	
Alterations [provisional]				
143				



				NCDTSL01/	2024
	Unit	Quantity	Rate	Amount	
Building up of openings Unless otherwise described, the wording "Build up existing openings" shall be deemed to include for preparing of existing surfaces, building up brickwork or blockwork, toothing and bonding to existing brickwork or blockwork, wording up of existing work and					
brickwork or blockwork, wedging up of existing work and repairing of existing surfaces on both sides as described.					
Existing material to become property of the contractor					
All existing material from the alterations which are not described as "Re-use" or "Hand over" shall be deemed to be the property of the contractor.					
Existing material must be carted away and included in the rates					
Existing material from the alterations which are not described as "Re-use" or "Hand over" and all rubble, must be carted away on regular intervals and not stored on site.					
Existing material shall not be re-used No existing material shall be allowed to be re-used if not described as "Re-use".					
Existing material must be set aside for re-use					
Material described as "set aside for re-use" shall mean that special care must be taken in the removal of any material earmarked for re-use and must be stored in a dry and protected place, until it is needed. Damage to material earmarked for re-use during the removal, store and refixing thereof shall be for contractor's expense.					
Handing over of existing material					
Where existing materials are described as "Hand over", such material must be carefully removed and stored until handing over thereof to the Employer. The contractor must get an official receipt from the Employer when handing over material or articles to the Employer. The date of handing over of the specific materials or articles must be stated on the receipt. If the contractor cannot produce the receipt when needed, it will be assumed that the materials are in his possession and he will be held responsible by the Employer for the replacement value thereof and this amount will be deducted from any payment from the Employer to the contractor.					
Removal and/or disposal of asbestos					
The Contractor will remove and/or dispose all existing asbestos items in strict accordance with the regulations regarding the removal and disposal of asbestos laid down by the government.					
Carried to Collection Section No. 2 Bill No. 1			R		
Alterations [provisional]					
144				ıl	1



					NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
	The Contractor will also refer and adhere to the Health					
	and Safety Specification regarding the removal and/or disposal of asbestos.					
	Rates for the removal and/or disposal of asbestos items shall be deemed to include for all prescibed regulations regarding removal and/or disposal of asbetos-related items.					
	Service and repair					
	The purpose of service and repair an item is to leave such an item in a perfectly working order on completion of the works, therefor the term "service and repair" includes a thorough inspection of the current working order of the item, identifying any defects and defect components, preparation of the affected area before rectifying the defects, rectifying the defects and replacing defect components with new components.					
	REMOVE EXISTING WORK					
	DOORS					
	Take off and remove existing doors with and including frames from walls					
1	Timber single door and metal frame, overall approximately 900mm wide x 2100mm high, from one brick walls	No	3			
	GRILLES, GATES, ETC.					
	Take off and remove existing steel grilles, gates, cages, etc. bolted to brick walls and/or concrete floors					
2	Steel security screen, size overall approximately 1300mm wide x 1500mm high, bolted to face brick wall	No	3			
3	Steel security screen, size overall approximately 1000mm wide x 800mm high, bolted to face brick wall	No	2			
	FLOOR FINISHES					
	Take up and remove existing floor finishes, including all underlays, bitumen, glue, cementious adhesives and all other adhesives leaving the exposed surface free from any underlays, adhesives, debris, dirt, etc.					
4	Vinyl tiles, including timber skirtings and quadrants	m²	50			
5	Ceramic floor tiles, including timber skirtings and quadrants	m²	6			
	Carried to Collection			R		
	Section No. 2					
	Bill No. 1					
	Alterations [provisional]					
	145					



		R & F	R AT COLESBE	RG WEIGHBR	IDGE - Principal Con NCDTSL01/2	
		Unit	Quantity	Rate	Amount	
	WALL FINISHES					
	Hack up/off and remove existing tiles, including all cementious adhesives and all other adhesives leaving the exposed surface free from any adhesives, debris, dirt, etc.					
6	Ceramic tiles from plastered walls	m²	1			
	CEILINGS	•••	'			
	Take down and remove existing fibre cement, gypsum or soft board ceilings					
7	Nailed-up ceilings, complete with and including cornices, from existing timber brandering	m²	56			
	<u>FITTINGS</u>					
	Take out and remove fittings					
8	Damaged floor cupboard, approximately 1250mm long x 600mm deep x 900mm high	No	1			
	SANITARY FITTINGS					
	Take out/off and remove sanitary fittings, including disconnecting pipes from fittings and making good existing floor and wall structures (new floor and wall finishes elsewhere measured)					
	From cement screeded floors and plastered walls					
9	Vitreous China WC suite, comprising pan and uPVC cistern and steel cistern cage bolted to external face of adjacent external wall, complete with and including flush pipe, service pipes, stop cocks, angle regulating valves, sewer pipes, etc.; repair holes in brick wall (face brick external and plaster internal) where cistern, cistern cage and flush pipe are removed with and including 3:1 cement mortar, coloured to match colour of existing face brick, finished smooth and flush with adjacent plastered and face brick surfaces	No	2			
	From plastered walls					
10	Wall mounted Vitreous China wash hand basin, complete with and including wall brackets, pillar taps, service pipes, traps, waste pipes, etc.	No	2			
	Carried to Collection			R		
	Section No. 2 Bill No. 1			K		
	Alterations [provisional] 146					
I	170		1	ļ	į į	



SANITARY PLUMBING Take out/off and remove waste pipes and pipe fittings (i.e. bends, junctions, etc.), traps, etc., including disconnecting pipes from fittings and making good sxisting floor and wall finishes 11 wPVC pipes not exceeding 50mm diameter from plastered walls 12 Bib traps from plastered walls 13 Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm brick wall, including disconnection of electrical supply No 1 Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]			ı			NCDTSL01/	2024
Take out/off and remove waste pipes and pipe fittings (i.e. bends, junctions, etc.), traps, etc., including disconnecting pipes from fittings and making good existing floor and wall finishes 10 uPVC pipes not exceeding 50mm diameter from plastered walls 11 Bib taps from plastered walls 12 Bib taps from plastered walls 13 Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm brick wall, including disconnection of electrical supply 14 No. 1 Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]			Unit	Quantity	Rate	Amount	
fittings (i.e. bends, junctions, etc.), traps, etc., including disconnecting pipes from fittings and making good existing floor and wall finishes 11 uPVC pipes not exceeding 50mm diameter from plastered walls 12 Bib taps from plastered walls No 2 MECHANICAL EQUIPMENT 13 Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm brick wall, including disconnection of electrical supply No 1 Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]		SANITARY PLUMBING					
plastered walls MECHANICAL EQUIPMENT Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm bnck wall, including disconnection of electrical supply No 1 Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]		fittings (i.e. bends, junctions, etc.), traps, etc., including disconnecting pipes from fittings and					
MECHANICAL EQUIPMENT Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm brick wall, including disconnection of electrical supply No 1 Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]	11		m	6			
Remove existing air conditioning unit, approximately 700mm wide 600mm high, from 230mm brick wall, including disconnection of electrical supply No 1 Carried to Collection R Section No. 2 Bill No. 1 Alterations [provisional]	12	Bib taps from plastered walls	No	2			
Carried to Collection Section No. 2 Bill No. 1 Alterations [provisional]		MECHANICAL EQUIPMENT					
Section No. 2 Bill No. 1 Alterations [provisional]	13	700mm wide 600mm high, from 230mm brick wall,	No	1			
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]							
Section No. 2 Bill No. 1 Alterations [provisional]		Openited to Oplication			_		
Alterations [provisional]					R		



			Amount	
BILL NO. 1 ALTERATIONS [PROVIS	SIONAL]			
COLLECTION		Page No		
	Brought Forward from Page	143 144		
		145		
		146 147		
	Carried To Section Summary	R		
Section No. 2 Bill No. 1 Alterations [provisional]				
	148			



ı	I		1		NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
	SECTION NO. 2					
	BUILDING WORKS					
	BILL NO. 2					
	ROOF COVERINGS					
	NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent					
	NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors					
	PROFILED METAL SHEETING AND ACCESSORIES					
	0.8mm Z275 spelter galvanised IBR steel sheets in single lengths with "chromadek" finish of approved standard colour on one side and standard grey backing finish on reverse side, fixed to timber purlins or rails					
1	Roof covering with pitches not exceeding 25 degrees	m²	92			
	0.8mm Z275 spelter galvanised IBR steel sheets accessories to preceding roof covering with "chromadek" finish of approved standard colour on one side and standard grey backing finish on reverse side, fixed to timber purlins or rails					
2	Ridge capping 650mm girth	m	10			
3	Valley covering 650mm girth	m	24			
	ROOF AND WALL INSULATION					
4	Double sided reflective aluminium foil faced insulation barrier, with reflective facing to be exposed to roof sheets	m²	56			
5	30mm Flexible faced polyisocyannaurate insulation boarding, laid over purlins (at approximately 600mm centres) and fixed concurrent with roof covering,					
	including holes through boards etc	m²	56			
	Carried To Section Summary					
	Section No. 2			R		
	Bill No. 2					
	Roof Coverings					
	149					



		I.	ı	NCDTSL01/	2024
	Unit	Quantity	Rate	Amount	
SECTION NO. 2					
BUILDING WORKS					
BILL NO. 3					
CARPENTRY AND JOINERY					
NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent					
NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors					
SUPPLEMENTARY PREAMBLES					
<u>Fixing</u>					
Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned to brickwork or concrete					
Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere					
<u>Joinery</u>					
Descriptions of frames shall be deemed to include frames, transomes, rails, etc					
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts					
Decorative thermosetting plastic laminate covering					
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish					
ROOFS ETC					
<u>Sundries</u>					
Two coats carbolineum on sawn timbers	m²	148			
PLATE NAILED TIMBER ROOF TRUSS CONSTRUCTION ETC					
SUPPLEMENTARY PREAMBLES					
Trusses are at maximum 900mm centres					
Roof coverings are on purlins					
Ceilings are plasterboard and fibre cement on 38 x 38mm brandering					
Carried to Collection			R		
Section No. 2			"		
Bill No. 3					
Carpentry And Joinery					
150					



		R&R	AT COLESBE	RG WEIGHBR	IDGE - Principal Contra NCDTSL01/20	
		Unit	Quantity	Rate	Amount	
	References given in descriptions refer to the respective types of trusses detai					
	References given in descriptions refer to the respective types of trusses detailed on the architect's/engineer's drawings for tender purposes					
	Dimensions in descriptions of trusses are nominal and actual measurements are to be obtained from the architect/engineer and/or taken on site before design or fabrication commences					
	Design Responsibility					
	The contractor shall be responsible for the design of the timber roof construction. The contractor will submit shop drawings for approval to the engineer/architect within two weeks after the date of appointment. The contractor shall commence manufacturing only after written approval of shop drawings from the engineer /architect					
	Timber roof construction					
	The following is applicable in respect of prefabricated timber roof truss construction:					
	Site inspection and liaison with main contractor					
	The trusses subcontractor is advised to liaise with the main contractor on site and confirm all the dimensions prior to design, fabrication and installation of the timber roof structures					
	Plate nailed timber roof truss construction					
	Sawn softwood grade 6 S.A Pine					
2	228 x 38mm Common rafters in lengths not exceeding 6.6m	m	122			
3	Roof construction to L shaped double pitched roof complete with two gable end two sides and hipped on the other, 6,21 x 8.6m and 2.67 x 3.60m overall on plan and 1860mm high overall, including trusses, jack rafters, permanent bracing and 50 x 75mm purlins at 600mm centres, etc., for roof sheeting.	No	1			
	EAVES, VERGES, ETC					
	Medium density plain fibre-cement fascias and barge boards					
4	225 x 12mm Fascias and barge boards, including galvanised steel profile joiners	m	45			
	Carried to Collection			R		
	Section No. 2 Bill No. 3 Corporate And Joinese					
	Carpentry And Joinery 151					



					NCDTSL01/2	2024
		Unit	Quantity	Rate	Amount	
	Trusses are at maximum 1 500mm centres. Roof covering to be IBR (0.8mm) thick approved light industrial Z275 spelter "Chromadek" galvanised steel sheeting (by others). Gypsum plaster board and fibre cement ceilings and / or suspended ceilings will be installed below roof trusses (ceilings elsewhere measured)					
	The dimensions in the descriptions of the roofs are scaled and are only a broad indication of the scope of the works. The contractor is required to obtain actual measurements from the Architect and/or the site before design or fabrication commences. Rates to include for complete roof structures including all fixing, hoisting, all rafter end splaying, wall plates, battens, edge battens, bracing, ridge rafters, valley rafters, etc					
	DOORS ETC					
	Wrought meranti doors hung to timber frames					
5	44mm 'C.K.S.' Framed batten door 2032 x 813mm high of 150 x 44mm top rail and stiles, 150 x 16mm middle ledge and braces and 230 x 22mm bottom ledge filled in with 22mm V jointed one side boarding filled in at the back with plywood veneer	No	2			
	40mm Semi-solid flush doors with 3,2mm plain hardboard covering on both sides and two concealed edges, hung to timber frames					
6	Door 813 x 2032mm high	No	2			
	<u>FITTINGS</u>					
	CUPBOARDS TO KITCHENS, SHELVING, DESKS, ETC					
	SUPPLEMENTARY PREAMBLES					
	<u>General</u>					
	The following fittings are given as complete units i.e. the components of the units have not been given separately. Descriptions of such units shall, therefore, be deemed to include all components, assembling, housing, notching, glueing, blocking, planting-on and screwing with countersunk screws, edge strips, thermosetting plastic laminate, glass, ironmongery, metalwork, paint or varnish finishes, etc					
	<u>References</u>					
	References given in descriptions refer to the respective types of fittings detailed on the architect's drawings accompanying these bills of quantities for tender purposes					
	Carried to Collection Section No. 2 Bill No. 3			R		
	Carpentry And Joinery					
	152					



1		l			NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
	Shelving with SA Pine framing, shelves, side and back panels, etc., complete as per Architect's Drawings					
7	600 x 32mm Thick 'Formica Lifeseal' timber worktop modern square profile with tight radius and edging strip on sides complete including 30 x 30 x 2mm mild steel bracket, bolts, etc.	m	7			
8	Floor drawer cupboard 2670 x 900mm high overall with sides, bottom, division, shelves, doors, framework, etc	No	1			
	Shelves consisting of shelves, frame, marine ply timber base with 2mm brushed aluminium kick plate, 19mm hardwood backboard, 8mm pins, etc., complete as per architect's drawings					
9	Floor open shelve cupboard 3350 x 900mm high with, sides, bottom, back, timber slats to face counter, etc	No	1			
	Carried to Collection Section No. 2			R		
	Section No. 2 Bill No. 3					
	Carpentry And Joinery					
	153					



BILL NO. 3 CARPENTRY AND JOINERY COLLECTION Brought Forward from Page 150 151 152 153 Carried To Section Summary Section No. 2 Bill No. 3 Carpentry And Joinery 154	1			NCDTSL01/	/2024
Carried To Section Summary Section No. 2 Bill No. 3 Carpentry And Joinery				Amount	
Carried To Section Summary Section No. 2 Bill No. 3 Carpentry And Joinery					
Carried To Section Summary Section No. 2 Bill No. 3 Carpentry And Joinery					
Brought Forward from Page 150 151 152 153 153 153 153	BILL NO. 3				
Brought Forward from Page 150 151 152 153 153 153 153	CARPENTRY AND JOIN	<u>ERY</u>			
Brought Forward from Page 150 151 152 153 Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery					
Brought Forward from Page 150 151 152 153 Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery			Dogo No		
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery			Page NO		
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery					
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery					
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery		Brought Forward from Page	150		
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery			151		
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery					
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery			152		
Carried To Section Summary R Section No. 2 Bill No. 3 Carpentry And Joinery			153		
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Section No. 2 Bill No. 3 Carpentry And Joinery					
Bill No. 3 Carpentry And Joinery		Carried To Section Summary	R		
Carpentry And Joinery					
	l l				
154	Carpentry And Joinery				
		154			



1	1	į į		NCDTSL01/	2024
	Unit	Quantity	Rate	Amount	
SECTION NO. 2					
BUILDING WORKS					
BILL NO. 4					
CEILINGS PARTITIONS AND ACCESS FLOORING					
SUPPLEMENTARY PREAMBLES					
<u>Fixing</u>					
Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete					
Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given elsewhere					
<u>Ceilings</u>					
Unless otherwise described ceilings shall be deemed to be horizontal					
<u>Bulkheads</u>					
Unless otherwise described bulkheads shall be deemed to be horizontal along the length					
Steel components					
All steel components for ceilings, partitions, etc are to be galvanised in accordance with SANS 121	•				
NAILED-UP CEILINGS					
SUPPLEMENTARY PREAMBLES					
<u>Openings</u>					
Prices for openings for light fittings, ventilation grilles, air conditioning diffusers, etc are to include for any necessary additional support, trimming around, etc					
6.4mm Gypsum plaster board ceilings					
Ceilings nailed on and including BPB Gypsum steel brandering in one direction at 400mm centres with 36 x 6mm meranti cover strips on joints	m²	56			
Extra over ceiling for 600 x 600mm Gypsum plaster	Na	2			
board trap door	No	2			
Gypsum plasterboard cornices					
75mm Coved cornices	m	41			
Glass mineral wool cavitybatt insulation					
405mm Insulation laid on top of brandering between root timbers etc	m²	56			
Carried To Section Summary	,		R		
Section No. 2					
Bill No. 4					
Ceilings Partitions And Access Flooring					
155					



					NCDTSL01/	/2024
		Unit	Quantity	Rate	Amount	
	SECTION NO. 2					
	BUILDING WORKS					
	BILL NO. 5					
	IRONMONGERY					
	NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent					
	NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors					
	SUPPLEMENTARY PREAMBLES					
	Proprietary items					
	Where applicable the manufacturers' names or product catalogue titles are given in sub-headings preceding the items					
	Prices are to be based on the specific products/articles specified. If tenderers wish to offer alternative products/articles for certain items, these items are to be clearly marked and the alternative specification given with supporting brochures etc clarifying the features of the products/articles offered					
	On request returnable samples are to be provided to the principal agent for consideration					
	HINGES, BOLTS, ETC					
	<u>"Solid"</u>					
1	Nickel plated flush bolt with keep fixed to metal	No	3			
	<u>"Union"</u>					
2	'37651AS' WC indicator bolt and keep	No	2			
	LOCKS					
	<u>"Solid"</u>					
3	76mm Four lever upright mortice lock (Code 313/A40)	No	3			
	<u>"Union"</u>					
4	Three lever deadlock escutcheon (Code 32320-78)	No	2			
	HANDLES					
	<u>"Solid"</u>					
5	'WATERBOK' Lever handle (Code 472/E41) on and including back plate with key hole	No	2			
	Corried to Collection			5		
	Carried to Collection Section No. 2			R		
	Bill No. 5					
	Ironmongery					
	156					



		Unit	Quantity	Rate	Amount	2024
6	"Union" Spring loaded 'ESCO ILEX SS' design lever handle (Code E-616204-05SS) -PAIR PINNING BOARDS, WRITING BOARDS,	No	3			
7	PROJECTION SCREENS, ETC Pinning board 2100 x 900mm high comprising of 12mm thick softboard clad in felt material, finished with 25mm natural anodised aluminium frame, plugged to wall	No	2			
8	BATHROOM FITTINGS 130 x 135 x 360mm Deep white powder coated lockable two roll holder, plugged	No	2			
9	115 x 270 x 110mm Deep stainless steel hand free soap dispenser, plugged	No	2			
10	350 x 365 x 230mm Deep stainless steel paper towel dispenser, plugged	No	2			
11	12 Litre stainless steel heavy duty pedal bin with removable plastic bucket	No	1			
12	"Halcast" Chromium plated lockable toilet roll holder plugged to walls screwed on 178 x 127 x 19mm hardwood block (Code 3665)	No	2			
	LETTERS, NAMEPLATES, ETC 3mm Thick white Perspex panel fixed to door with stainless steel dome nuts					
13	60 x 30 x 2mm Perspex plate with engraved 20mm high black text or numerals	No	5			
	SUNDRIES "Solid"					
14	38mm Diameter rubber door stop plugged	No	5			
	Carried to Collection			R		
	Section No. 2 Bill No. 5			, and the second		
	Ironmongery 157					



			NCDTSL01/	2024
			Amount	
BILL NO. 5				
<u>IRONMONGERY</u>				
COLLECTION				
		Page No		
	Drought Forward from Dogo	450		
	Brought Forward from Page	156		
		157		
	0 1 17 0 4 0			
_	Carried To Section Summary	R		
Section No. 2				
Bill No. 5				
Ironmongery				
	158			



SECTION NO. 2 BUILDING WORKS BILL NO. 6 METALWORK NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions Descriptions of botts shall be deemed to include nuts and washers. Descriptions of expansion anchors and botts and chemical anchors and hottshall be deemed to include nuts, washers and mortices in brickwork or concrete litems described as blouged shall be deemed to include nuts, washers and mortices in brickwork or concrete litems described as plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall be only with SAGGA regulations used to the server of thicknesses shall be safety glass as shown on the schedules/drawings appended to these bills of quantities. Glass thickness shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities. The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacture/contractor supplying the architectural aluminium product Carried to Collection Expection No. 2 Bill No. 6 Metalwork			1		NCDTSL01/2	2024
BUILDING WORKS BILL NO.6 METALWORK NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent. NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions of botts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'hotged shall be deemed to exclude the bolts unless otherwise described Items described as 'hotged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings appended to these bills of quantities. Glass thickness shall be personally with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities. The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product		Unit	Quantity	Rate	Amount	
BUILDING WORKS BILL NO.6 METALWORK NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent. NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions of botts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'hotged shall be deemed to exclude the bolts unless otherwise described Items described as 'hotged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings appended to these bills of quantities. Glass thickness shall be personally with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities. The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product						
BILL NO. 6 METALWORK NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions Descriptions of botts shall be deemed to include nuts and washers Descriptions of expansion anchors and botts and chemical anchors and bottsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for bolf(s)' shall be deemed to exclude the botts unless otherwise described Items described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities. The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork						
METALWORK NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions of boits shall be deemed to include nuts and washers Descriptions of expansion anchors and boits and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for boit(s)' shall be deemed to exclude the boits unless otherwise described Items described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings appended to these bills of quantities. Glass thickness shall be personed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork						
NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions Descriptions of botts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Itlems described as "holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described litems described as "holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described litems described as "holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described litems described as "holed for bolt(s)" shall be deemed to exclude screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shall be premoved only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product						
a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltshall be deemed to include nuts, washers and mortices in brickwork or concrete Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Itlems described as 'holed provides as the standard to exclude the bolts unless otherwise described Itlems described as 'holed provided provide	METALWORK					
Preambles for Trades 2008 published by the Association of South African Quantity Surveyors SUPPLEMENTARY PREAMBLES Descriptions Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Items described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork	a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the					
Descriptions Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described ltems described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities. The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork	Preambles for Trades 2008 published by the					
Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Items described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork	SUPPLEMENTARY PREAMBLES					
and washers Descriptions of expansion anchors and bolts and chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete Items described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described Items described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork	<u>Descriptions</u>					
chemical anchors and boltsshall be deemed to include nuts, washers and mortices in brickwork or concrete ltems described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described ltems described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork						
ltems described as 'plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork	chemical anchors and boltsshall be deemed to include					
screwing to fibre, plastic or metal plugs at not exceeding 600mm centres Aluminium doors, windows, etc Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Carried to Collection R Metalwork						
Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork	screwing to fibre, plastic or metal plugs at not exceeding					
criteria Glazing shall comply with SAGGA regulations. Glass shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork	Aluminium doors, windows, etc					
shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork						
tape and plastic and shall be removed only once surrounding trades have been completed For purpose made windows and doors, refer to drawings annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection R Section No. 2 Bill No. 6 Metalwork	shall be safety glass as shown on the window schedules/drawings appended to these bills of quantities. Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the					
annexed to these bills of quantities The following certificates shall be provided prior to commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork	tape and plastic and shall be removed only once					
Commencement of site work 1. A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork						
Certificate from the manufacturer/contractor supplying the architectural aluminium product Carried to Collection Section No. 2 Bill No. 6 Metalwork						
Section No. 2 Bill No. 6 Metalwork	Certificate from the manufacturer/contractor supplying					
	Section No. 2 Bill No. 6			R		
	159					



1					NCDTSL01/2	ZUZ4
		Unit	Quantity	Rate	Amount	
	A Certificate of Conformance confirming that anodising or powder coating has been processed in					
	accordance with SANS 999 and SANS 1796 respectively					
	3. A powder guarantee of not less than 15 years issued by the powder manufacturer. The specific conditions contained in this guarantee shall form part of the powder coating process					
	4. A Certificate of Conformance confirming that glazing has been installed in accordance with SANS 0137, ensuring that safety glazing materials have been installed in the mandatory areas and that each individual pane of safety glazing materials has been permanently marked					
	5. A warranty from the manufacturer of the laminated safety glass and/or hermetically sealed glazing units guaranteeing the products against delamination and colour degredation for a period of not less than five years					
	NOTE: All tenderers are referred to architect's drawings and details based on these bills of quantities for tender purposes					
	GALVANISED MILD STEEL GATES, SCREENS, ETC					
1	Purpose-made single gate 1190 x 2021mm high of 50 x 25 x 2.5mm hollow section frame filled in with 12mm diameter mild steel bars placed at 100mm centres vertically and welded to frame and fitted with a pair of suitable hinges welded to post and with hasp and staple welded on (G02)	No	2			
	STEEL ROLLER SHUTTERS ETC					
	"WISPECO Roll-A-Door" galvanised steel with chromadek coated finish fire rated roller shutters or other equal approved, with 76mm slats (18kg/m²) fixed to brickwork or concrete					
2	Manual push-up slatted roller shutter for 900 x 1200mm high opening	No	1			
	Carried to Collection			R		
	Section No. 2 Bill No. 6					
	Metalwork					
	160					
I	.50		ı l	l	ıl İ	l



		NCDTSL01/2	2024
BILL NO. 6 METALWORK COLLECTION	Page No	Amount	
Brought Forward from Page	159 160		
	_		
Carried To Section Summary Section No. 2 Bill No. 6 Metalwork 161	R		



					NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
	SECTION NO. 2					
	BUILDING WORKS					
	BILL NO. 7					
	TILING					
	NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent					
	NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors					
	SUPPLEMENTARY PREAMBLES					
	<u>Fixing</u>					
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding					
	Tiling described as "fixed with adhesive on power floated concrete" shall be deemed to include for approved tiling key-coat					
	Ceramic, porcelain, marble and granite tiles are to be fixed and grouted with suitable adhesives and grouts as recommended by the manufacturer of the tiles					
	WALL TILING					
	"Johnson" 200 x 200 x 5mm White Glazed "A" Grade ceramic tiles fixed with adhesive to plaster (plaster elsewhere) and flush pointed with white waterproof antifungal grout					
1	On walls in isolated panels, splashbacks, etc not exceeding 1m	m²	2			
2	Fair exposed cutting and fitting around pipe not exceeding 100mm internal diameter	No	4			
3	Fair exposed cutting and fitting around pipe exceeding 100mm and not exceeding 150mm internal diameter	No	2			
	FLOOR TILING 600 x 600 x 15mm Non-slip 'UNION' Porcelain tiles fixed with adhesive and flush pointed with tinted waterproof jointing compound					
4	On floors and landings	m²	56			
	Carried To Section Summary Section No. 2 Bill No. 7 Tiling			R		
	162					



	R&R	AT COLESBI	ERG WEIGHBR	IDGE - Principal Contract NCDTSL01/2024
	Unit	Quantity	Rate	Amount
SECTION NO. 2				
BUILDING WORKS				
BILL NO. 8 PLUMBING AND DRAINAGE				
NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent				
NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors				
SUPPLEMENTARY PREAMBLES				
Copper pipes:				
Pipes shall be hard drawn and half-hard pipes of the class stated. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), class 2 (half-hard) and class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground				
Lead pipes and traps				
All soldered joints shall be wiped and brass unions shall be used for jointing lead to steel				
Reducing fittings				
Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained				
Wire gratings				
Descriptions of gutter outlets etc shall be deemed to include wire balloon gratings				
Septic tanks				
Descriptions of gutter outlets etc shall be deemed to include wire balloon gratings				
Carried to Collection			R	
Section No. 2				
Bill No. 8				
Plumbing And Drainage				
163				



	ı			NCDTSL01/2
	Unit	Quantity	Rate	Amount
Exposed concrete surfaces				
Exposed surfaces of concrete stormwater channels, cover slabs, inspection eye marker slabs, gulley tops, cleaning eye tops, catchpits, inspection chambers, etc shall be finished smooth with plaster				
Excavations				
No claim for rock excavation will be entertained unless the contractor has timeously notified the quantity surveyor thereof prior to backfilling				
'Soft rock' and 'hard rock' shall be as defined in 'Earthworks'				
Laying, backfilling, bedding, etc. of pipes				
Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions				
Where no manufacturers' instructions exist pipes shall be laid in accordance wi				
Where no manufacturers' instructions exist pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following:				
SABS/SANS 1200 L : Medium-pressure pipelines				
LD : Sewers				
LE : Stormwater drainage				
Pipe trenches etc shall be backfilled in accordance with				
clauses 3, 5.5, 5.6, 5.7 and 7 of SABS/SANS 1200				
DB : Earthworks (Pipe trenches)				
Pipes shall be bedded in accordance with clauses 3.1 to				
3.4.1, 5.1 to 5.3 and 7 of SABS/SANS 1200				
LB : Bedding (Pipes).				
Unless otherwise described bedding of rigid pipes shall				
be class B bedding				
Flush pans				
Flush pans shall have straight or side outlets and 'P' or 'S' traps as necessary				
Stainless steel basins, sinks, wash troughs, urinals, etc.				
Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable				
Carried to Collection Section No. 2			R	
Bill No. 8				
Plumbing And Drainage				
164				1



I				5 .	NCDTSL01	/2024
		Unit	Quantity	Rate	Amount	
	RAINWATER DISPOSAL					
	0.6mm Galvanised sheet iron					
1	100 x 75mm Roof gutters with beaded front edge	m	44			
2	Extra over gutter for stopped end	No	6			
3	Extra over gutter for angle	No	6			
4	Extra over gutter for outlet for 80mm diameter pipe	No	6			
	PVC pipes					
5	80mm Diameter rainwater downpipes	m	14			
	Extra over PVC pipes for fittings					
6	80mm Bend	No	6			
7	80mm Tee junction	No	6			
	SANITARY FITTINGS					
	<u>'Vaal'</u>					
8	Close coupled 90 degrees outlet wall hung open rim washdown pan (Code 750200) and matching 9 litre cistern (Ccode 7116LP)complete with lid, fitments and flush pipe elbow and heavy duty A1 high traffic toilet seat cover for, colour white	No	2			
9	510x 405mm Vitreous china 'Hibiscus' basin with three semi-punched tapholes, integrated overflow and chainstay hole through centre bolted to wall with two 10mm bolts, colour white	No	2			
	WASTE UNIONS ETC					
10	32mm Basin waste union	No	2			
11	32mm Bottle trap	No	2			
	TRAPS ETC					
	'Flexitraps':					
12	32 x 40mm Reseal 'P' or 'S' trap	No	2			
	TAPS, VALVES, ETC					
	'Cobra Watertech'					
13	15mm 126CP stopcock	No	4			
14	15mm Star wall mounted chromium plated swan neck swivel sink mixer (Code CSS 115)	No	2			
	Carried to Collection			R		
	Section No. 2					
	Bill No. 8					
	Plumbing And Drainage					
	165					



1			1	1	NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
15	15mm chromium plated angle regulating valve and flexible connection pipe	No	4			
	SANITARY PLUMBING					
	PVC-U Soil and vent pipes					
16	50mm pipe	m	6			
17	110mm Pipes	m	18			
18	110mm Pipes laid in and including trenches not exceeding 1m deep	m	22			
	Extra over PVC-U soil and vent pipes for fittings					
19	50mm Bend	No	4			
20	50mm Junction	No	2			
21	50mm Access bend	No	2			
22	110 x 50mm Reducing junction	No	2			
23	110mm Bend	No	8			
24	110mm Pan connector	No	4			
25	110mm Access junction	No	2			
26	110mm Access reducing junction	No	2			
	<u>Testing</u>					
27	Sundries Testing waste pipe system	Item				
	WATER SUPPLIES					
	Class 0 copper pipes					
28	22mm Pipes	m	18			
29	32mm Pipes	m	12			
30	22mm Pipes chased in walls	m	16			
31	32mm Pipes chased in walls	m	8			
	Extra over class 0 copper pipes for capillary fittings					
32	22mm Fittings	No	4			
33	32mm Bend	No	6			
34	32mm Junction	No	8			
	Carried to Collection			R		
	Section No. 2 Bill No. 8					
	Plumbing And Drainage					
	166					



		R&R	AT COLESB	ERG WEIGHBR	RIDGE - Principal Cor NCDTSL01/	
		Unit	Quantity	Rate	Amount	
35	system with vacuum tubes and electric backup for long cold seasons	No	1			
	FIRE APPLIANCES ETC					
36	4.5kg Dry chemical powder fire extinguisher	No	2			
	Carried to Collection Section No. 2 Bill No. 8 Plumbing And Prainage			R		
	Plumbing And Drainage 167					
- 1	·		ı	1	11	I



ı		1	NCDTSL01/	2024
			Amount	
BILL NO. 8				
PLUMBING AND DRAINA	AGE			
				
COLLECTION				
		Page No		
		l ago ito		
	Prought Forward from Page	163		
	Brought Forward from Page	103		
		164		
		165		
		166		
		100		
		167		
	Carried To Section Summary	R		
Section No. 2	/			
Bill No. 8				
Plumbing And Drainage	400			
	168			



		Unit	Quantity	Rate	Amount	2024
		Offic	Quality	Nate	Amount	
	SECTION NO. 2					
	BUILDING WORKS					
	BILL NO. 9					
	GLAZING					
	NOTE: The use of trade names simply serves to indicate a standard acceptable to the Principal Agent. Any other brand may be used with prior written approval of the Principal Agent					
	NOTE: Tenderers are advised to study the Model Preambles for Trades 2008 published by the Association of South African Quantity Surveyors					
	SUPPLEMENTARY PREAMBLES					
	Float glass					
	The term 'float glass' is used for monolithic annealed glass					
	Laminated glass					
	Laminated glass to have polyvinyl butyral (PVB) interlayer(s)					
	GLAZING TO STEEL WITH PUTTY					
	6mm Clear float safety glass					
1	Panes exceeding 0,5m² and not exceeding 2m²	m²	6			
	6mm Obscure glass					
2	Panes exceeding 0,5m² and not exceeding 2m²	m²	2			
	TOPS, SHELVES, DOORS, MIRRORS, ETC					
	6mm Silvered float glass copper backed mirrors					
	with 1mm bevelled and polished edges, holed for and fixed with chromium plated dome headed mirror					
	screws with rubber buffers to plugs in brickwork or					
	concrete Minus 200 450 mm high					
3	Mirror 600 x 450mm high	No	2			
	Carried To Section Summary			R		
	Section No. 2					
	Bill No. 9 Glazing					
	169					
ı	l l		i .		ш	1



SECTION NO. 2 BUILDING WORKS BILL NO. 10 PAINTWORK NOTE: All tenderers are advised to study the Model Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Bilstered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Bilstered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Bilstered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Bilstered or peeling paint shall be completely removed and cracks and credities shall be porned, filled with suitable filler and finished smooth Previously painted wood surfaces Surfaces shall be primed, filled with suitable filler and finished smooth Paintwork To Existing Work On FLOATED PLASTER Prepare, apply one coat "Plascon Double Velvet VEL" non-drip polyurethane enamel paint On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dolub's uper acrylic PVA paint 2 On ceilings and cornices ON WOOD SURFACES Three coats "Woodoc 35'exteriors sealer Carried to Collection R Carried to Collection R Paintwork 170					NCDTSL01	/2024
BUIL DING WORKS BILL NO. 10 PAINTWORK NOTE: All tenderers are advised to study the Model Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL" non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux Super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Carried to Collection R Carried to Collection R Paintwork		Unit	Quantity	Rate	Amount	
BUIL DING WORKS BILL NO. 10 PAINTWORK NOTE: All tenderers are advised to study the Model Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL" non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux Super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Carried to Collection R Carried to Collection R Paintwork	SECTION NO. 2					
PAINTWORK NOTE: All tenderers are advised to study the Model Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dlux'super acrylic PVA paint 2 On ceilings and comices ON WOOD SURFACES Three coats "Woodoc 35'exteriors sealer Carried to Collection R Section No. 2 Bill No. 10 Paintwork						
NOTE: All tenderers are advised to study the Model Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL"non-drip polyurethane enamel paint 1 On internal walls m² 124 PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint Carried to Collection R Section No. 2 Bill No. 10 Paintwork	BILL NO. 10					
Preambles for Trades before pricing this bill PREPARATORY WORK TO EXISTING WORK Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL"non-drip polyurethane enamel paint 1 On internal walls m² 124 PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux' super acrylic PVA paint 2 On cellings and cornices m² 59 ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer 3 Doors m² 19 Carried to Collection Section No. 2 Bill No. 10 Paintwork	PAINTWORK					
Previously painted plastered surfaces Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL" non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection R Ection No. 2 Bill No. 10 Paintwork						
Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection R Section No. 2 Bill No. 10 Paintwork	PREPARATORY WORK TO EXISTING WORK					
to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth Previously painted metal surfaces Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls m² 124 PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint 2 On ceilings and cornices ON WOOD SURFACES Three coats "Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	Previously painted plastered surfaces					
Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished					
Blistered or peeling paint shall be completely removed down to bare metal Previously painted wood surfaces Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	Previously painted metal surfaces					
Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet YEL"non-drip polyurethane enamel paint On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats "Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats "Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	Blistered or peeling paint shall be completely removed					
peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth PAINTWORK TO EXISTING WORK ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls m² 124 PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices m² 59 ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors m² 19 Carried to Collection Section No. 2 Bill No. 10 Paintwork	Previously painted wood surfaces					
ON FLOATED PLASTER Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork R 124 Paintwork m² 124 Paintwork R R	peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and					
Prepare, apply one coat "Plascon Plaster Primer UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork R Ital	PAINTWORK TO EXISTING WORK					
UC65" and apply two coats "Plascon Double Velvet VEL"non-drip polyurethane enamel paint 1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint 2 On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork R 124 PAINTWORK m² 194 124 PAINTWORK The Coats Wood WORK ON PLASTER BOARD The Coats Universal undercoat and two coats 'Dulux'super acrylic PVA paint M² 194 The Coats 'Wood Coats' Universal undercoat and two coats 'Dulux'super acrylic PVA paint M² 194 Carried to Collection R Paintwork	ON FLOATED PLASTER					
1 On internal walls PAINTWORK ETC TO NEW WORK ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork	UC65" and apply two coats "Plascon Double Velvet					
ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	1 On internal walls	m²	124			
ON PLASTER BOARD One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork	PAINTWORK ETC TO NEW WORK					
One coat primer, one coat universal undercoat and two coats 'Dulux'super acrylic PVA paint On ceilings and cornices ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork R Feed to Coat universal undercoat and two coats and two coats universal undercoat and two coats and two coa						
ON WOOD SURFACES Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork	One coat primer, one coat universal undercoat and					
Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork	On ceilings and cornices	m²	59			
Three coats 'Woodoc 35'exteriors sealer Doors Carried to Collection Section No. 2 Bill No. 10 Paintwork Paintwork	ON WOOD SURFACES					
Doors m² 19 Carried to Collection Section No. 2 Bill No. 10 Paintwork						
Carried to Collection Section No. 2 Bill No. 10 Paintwork		m²	19			
Section No. 2 Bill No. 10 Paintwork						
Section No. 2 Bill No. 10 Paintwork						
Section No. 2 Bill No. 10 Paintwork						
Section No. 2 Bill No. 10 Paintwork						\vdash
Bill No. 10 Paintwork				R		
Paintwork						
	170					




					NCDTSL01/	2024
		Unit	Quantity	Rate	Amount	
	ON METAL SURFACES					
	One coat alkyd based zinc phosphate primer and					
	two coats premium quality polyurethane enamel paint, on steel					
4	On door frames	m²	6			
5	On windows with burglar bars	m²	17			
6	Gates, grilles, burglar screens, balustrades, etc (both	2				
	sides measured over the full flat area)	m²	9			
	Carried to Collection			R		
	Section No. 2			ĸ		_
	Bill No. 10					
	Paintwork					
	171					



I		ı	NCDTSL01/	2024
			Amount	
Bu 1 No 12				
BILL NO. 10				
<u>PAINTWORK</u>				
COLLECTION				
		Page No		
		1 490 140		
	Drought Command from Done	170		
	Brought Forward from Page	170		
		171		
	Carried To Section Summary	R		
Section No. 2				
Bill No. 10				
Paintwork				
	172			
	112			



	R & R AT COLESB	ERG WEIGHBR	IDGE - Principal Cor NCDTSL01/	
			Amount	
	0-0-10-11-11-11-11-11-11-11-11-11-11-11-			
	SECTION NO. 2			
	BUILDING WORKS SECTION SUMMARY			
Bill No.	SECTION SUMMARY	Page		
1	ALTERATIONS [PROVISIONAL]	148		
2	ROOF COVERINGS	149		
3	CARPENTRY AND JOINERY	154		
4	CEILINGS PARTITIONS AND ACCESS FLOORING	155		
5	IRONMONGERY	158		
		161		
6	METALWORK TILING	162		
7				
8	PLUMBING AND DRAINAGE	168		
9	GLAZING	169		
10	PAINTWORK	172		
	Carried to Final Summary Section No. 2	R		<u> </u>
	SECTION SUMMARY			
	173			
			I	1





SECTION NO. 3 EXTERNAL WORKS[PROVISIONAL]



1		1		NCDTSL01/2
	Unit	Quantity	Rate	Amount
SECTION NO. 3				
EXTERNAL WORKS[PROVISIONAL]				
BILL NO. 1				
<u>EARTHWORKS</u>				
SUPPLEMENTARY PREAMBLES				
Nature of ground				
User Note - The following are typical examples of descriptions of 'nature of ground'				
The nature of the ground is assumed to be loose sandy material, therefore 'earth', but possibly interspersed with 'soft rock' or 'hard rock'				
The nature of the ground is assumed to be gravel, therefore 'earth', but possibly interspersed with 'soft rock' or 'hard rock'				
The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, all of which will be deemed as 'earth', but possibly interspersed with 'hard rock'				
Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore 'earth'				
A soils investigation has been carried out on the site by the engineer and the report is annexed to these bills of quantities. The soils report indicates that the ground varies between silty sand, reworked soil of mixed origin and residual shale, all of which will be deemed as 'earth'. All very hard unweathered shale, ironstone, etc., the removal of which necessitates the use of explosives or heavy duty hydraulic percussion hammers (peckers), will be classified as 'hard rock'				
Subterranean water				
User Note - The following are typical examples of descriptions of 'subterranean water'				
No subterranean water is expected The water table is expected to vary between approximately ?m and ?m below natural ground level. The removal of subterranean water is given separately				
Excavation for working space in rock				
Notwithstanding clause 11 page 8 of the Standard System of Measuring Building Work, excavation for working space in rock will be measured in cubic metres to the extent executed and given as 'extra over' bulk excavation or trench and hole excavation as the case may be				
O-mi-da O-llordo			_	
Carried to Collection Section No. 3			R	
Bill No. 1				
וווט. ו				
Earthworks				



Carting away of excavated material Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site Filling Notwithstanding the reference to prescribed multiple handling or loading the page of of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates 1 Fance, 2400mm high, comprising of mesh flencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases 2 Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete 3 Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete 3 Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases 5 Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases 6 Streakance Etc Site clearance 4 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 2m deep 5 Holes Fatra over all excavations for carting away Carried to Collection Section No. 3 Bill No. 1 Earthworks 176			R&R	AT COLESBI	ERG WEIGHBR	IDGE - Principal Contract NCDTSL01/2024
Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, a tetrnatively, from stock piles situated on the building site Filling Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates 1 Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases 2 Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases 3 Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance 4 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth Extra over all excavations for carting away 6 Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Section No. 3 Bill No. 1 Earthworks			Unit	Quantity	Rate	II I
Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, a tetrnatively, from stock piles situated on the building site Filling Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates 1 Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases 2 Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases 3 Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance 4 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth Extra over all excavations for carting away 6 Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Section No. 3 Bill No. 1 Earthworks						
be deemed to include loading excavated material onto trucks directly from the execuations or, alternatively, from stock piles situated on the building site Filling Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases m 150 Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete 2 Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SIFE CLEARANCE ETC Site clearance 4 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		Carting away of excavated material				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes		be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from				
handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material User Note - When no information regarding density tests is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete Steel slicing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 20mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes Ma 300 EXCAVATION ETC Excavation in earth not excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		<u>Filling</u>				
is available the following preamble in respect of testing may be inserted Testing Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes May 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple				
Prices for filling are to include for all necessary density tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases No SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		is available the following preamble in respect of testing				
tests in accordance with SABS 1200D DEMOLITIONS ETC Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete No Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes May 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		Testing				
Dismantle and remove existing fence and gates Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases may be swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SiTE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 20mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes May 300 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks						
Fence, 2400mm high, comprising of mesh fencing, barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases x 2400mm high, including gate posts and concrete x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth may 100 mm in earth not exceeding 2m deep Holes material from excavations and/or stock piles on site, to a dumping site to be located by the contractor mish, and mish in the contractor site, to a dumping site to be located by the contractor Site of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks		DEMOLITIONS ETC				
barbed wire to top of mesh fence and steel posts, corner posts, etc., complete with and including concrete bases Double swing gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Carried to Collection Section No. 3 Bill No. 1 Earthworks		Dismantle and remove existing fence and gates				
x 2400mm high, including gate posts and concrete Steel sliding gate, overall approximately 4500mm wide x 2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes Mo Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks	1	barbed wire to top of mesh fence and steel posts, corner	m	150		
2400mm high, including gate posts and concrete bases SITE CLEARANCE ETC Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks	2		No	2		
Site clearance Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks	3		No	1		
Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc. and trees not exceeding 200mm girth EXCAVATION ETC Excavation in earth not exceeding 2m deep Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks		SITE CLEARANCE ETC				
hedges, shrubs, bush, etc. and trees not exceeding 200mm girth m² 300 EXCAVATION ETC Excavation in earth not exceeding 2m deep 5 Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations 7 Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks		Site clearance				
Excavation in earth not exceeding 2m deep Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks	4	hedges, shrubs, bush, etc. and trees not exceeding	m²	300		
Excavation in earth not exceeding 2m deep Holes m³ 10 Extra over all excavations for carting away Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks		EXCAVATION ETC				
Holes material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks						
Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks	5		m³	10		
Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks		Extra over all excavations for carting away				
site, to a dumping site to be located by the contractor m³ 3 Risk of collapse of excavations Sides of bulk excavations not exceeding 1,5m deep m² 68 Carried to Collection Section No. 3 Bill No. 1 Earthworks	6					
Sides of bulk excavations not exceeding 1,5m deep Carried to Collection Section No. 3 Bill No. 1 Earthworks R			m³	3		
Carried to Collection Section No. 3 Bill No. 1 Earthworks		Risk of collapse of excavations				
Section No. 3 Bill No. 1 Earthworks	7	Sides of bulk excavations not exceeding 1,5m deep	m²	68		
Bill No. 1 Earthworks		Carried to Collection			R	
Earthworks		Section No. 3				



		R&F	R AT COLESBI	ERG WEIGHBR	IDGE - Principal Contract NCDTSL01/2024
		Unit	Quantity	Rate	Amount
	Keeping excavations free of water				
8	Keeping excavations free of all water other than subterranean water	Item			
	FILLING ETC OTHER THAN BULK				
	Earth filling obtained from the excavations and/or				
	prescribed stock piles on site, compacted to 98% Mod AASHTO density				
9	Backfilling to trenches, holes, etc.	m³	1		
	SOIL POISONING				
	Soil insecticide in accordance with SANS 5859				
10	To bottoms and sides of trenches etc.	m²	85		
	Carried to Collection			R	
	Section No. 3				
	Bill No. 1 Earthworks				
	177				



		NCDTSL01/2	2024
BILL NO. 1 EARTHWORKS COLLECTION	Page No	Amount	
Brought Forward from Page	175 176 177		
Carried To Section Summary	R		
Carried To Section Summary Section No. 3	K		
Bill No. 1			
Earthworks 178			
170			



				NCDTSL01/	202
	Unit	Quantity	Rate	Amount	
SECTION NO. 3					
EXTERNAL WORKS[PROVISIONAL]					
BILL NO. 2					
CONCRETE, FORMWORK AND REINFORCEMENT					
SUPPLEMENTARY PREAMBLES					
Cost of tests					
The costs of making, storing and testing of concrete test cubes as required under clause 7 Tests of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the principal agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the principal agent. (Test cubes are measured separately)					
Breeze concrete					
Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated					
<u>Lightweight concrete</u>					
Lightweight concrete shall have a density of 600kg/m3 for the top 50mm and 400kg/m3 for the remaining thickness. The minimum thickness at outlets, channels, etc. shall be 50mm					
<u>Formwork</u>					
Descriptions of formwork shall be deemed to include use and waste only (except where described as 'left in' or 'permanent'), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use					
The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself					
Formwork to soffits of solid slabs etc. shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described					
Carried to Collection			В		
Section No. 3			R		<u> </u>
Bill No. 2					
Concrete, Formwork And Reinforcement					
179					
179				II	l



					NCDTSL01/2	2024
		Unit	Quantity	Rate	Amount	
	Formwork to soffits of slabs, beams, etc. shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described Formwork to sides of bases, pile caps, ground beams,					
	etc. will only be measured where it is prescribed by the engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in Earthworks					
	User Note - In order to accommodate the custom in some regions to give formwork to sides of beams, isolated beams, etc. separately from formwork to the soffits thereof, the items in respect of formwork to beams, isolated beams, etc. are given under the headings of 'Formwork to Sides', 'Formwork to Soffits' and 'Formwork to Sides and Soffits'					
	UNREINFORCED CONCRETE CAST ON/IN FORMWORK					
	20MPa/19mm concrete					
1	Bases	m³	3			
				_		
	Carried to Collection Section No. 3			R		
	Bill No. 2					
	Concrete, Formwork And Reinforcement 180					
ļ	100			l	l l	



		Amount	
BILL NO. 2			
CONCRETE, FORMWORK AND REINFORCEMENT			
COLLECTION			
	Page No		
	. ago . io		
Brought Forward from Page	179		
	180		
Carried To Section Summary	R		
Section No. 3			
Bill No. 2 Concrete, Formwork And Reinforcement			
181			



		1		NCDTSL01/20
	Unit	Quantity	Rate	Amount
SECTION NO. 3				
EXTERNAL WORKS[PROVISIONAL]				
BILL NO. 3				
<u>METALWORK</u>				
SUPPLEMENTARY PREAMBLES				
Descriptions of bolts, anchors, etc.				
Descriptions of bolts shall be deemed to include nuts and washers				
Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete				
Items described as 'holed for bolt(s)' shall be deemed to exclude the bolts unless otherwise described				
Items described as 'plugged' shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres				
Aluminium doors, windows, etc.				
Doors and windows shall comply with AAAMSA design criteria Glazing shall comply with SAGGA regulations. Glass shall be type? laminated performance glass as shown on the window schedules/drawings appended to these bills of quantities (as described in the headings to window descriptions?). Glass thickness shall comply with SAGGA regulations irrespective of thicknesses shown on the schedules/drawings Doors and windows shall be supplied with protective tape and plastic and shall be removed only once surrounding trades have been completed. For purpose made windows and doors, refer to drawings annexed to (issued separately with?) these bills of quantities				
The following certificates shall be provided prior to commencement of site work: 1 A copy of the relevant AAAMSA Performance Test Certificate from the manufacturer/contractor supplying the architectural aluminium product 2 A Certificate of Conformance confirming that anodising or powder coating has been processed in accordance with SANS 999 and SANS 1796 respectively				
Carried to Collection Section No. 3 Bill No. 3			R	
Metalwork				
182				



R & R AT COLESBERG WEIGHBRIDGE - Principal Contract NCDTSL01/2024 Linit Quantity Rate Amount

		Unit	Quantity	Rate	Amount
	3 A powder guarantee of not less than 15 years issued by the powder manufacturer. The specific conditions contained in this guarantee shall form part of the powder coating process 4 A Certificate of Conformance confirming that glazing has been installed in accordance with SANS 0137, ensuring that safety glazing materials have been installed in the mandatory areas and that each individual pane of safety glazing materials has been permanently marked 5 A warranty from the manufacturer of the laminated safety glass and/or hermetically sealed glazing units guaranteeing the products against delamination and colour degradation for a period of not less than five years				
	<u>FENCING</u>				
	ClearVu Invisible Wall or other approved galvanised high security fence system COATED with andincluding "Polymetic 6000" or other approved coating. Fence panels with bottom of fence let 100mm deep into ground, including all excavations and backfilling				
1	Panel, 3300mm wide x 2400mm high	No	47		
	Fence and gate posts with bottom of posts cast 600mm deep into bottom of concrete bases (elsewhere measured)				
2	Post, 3000mm long	No	47		
3	Gate post, 3000mm long	No	6		
	<u>Gates</u>				
4	Single gate, 1200mm wide x 2400mm high, hung one side equal, including one locking devices	No	1		
5	Double gate, 4500mm wide x 2400mm high, hung in two equal sized leaves, including two locking devices	No	2		
	<u>Sundries</u>				
6	Shark tooth spike topping, secured to top of fence panels, posts and gates	m	150		
7	Continuous galvanized barbed wire security roll to bottom of fence flat wrapped in 500mm diameter rings, tied together and to bottom of fence and let into ground, 600mm deep, including all excavations and backfilling	m	150		
	Carried to Collection Section No. 3 Bill No. 3 Metalwork			R	
	183				



1	ı	NCDTSL01/2	2024
		Amount	
BILL NO. 3 METALWORK			
COLLECTION			
	Page No		
Brought Forward from Page	182		
	183		
Carried To Section Summary	R		
Section No. 3 Bill No. 3			
Metalwork 184			
1		II I	1



			NCDTSL01	/2024
			Amount	
	SECTION NO. 3			
	EXTERNAL WORKS[PROVISIONAL]			
	SECTION SUMMARY			
Bill No.		Page		
1	EARTHWORKS	178		
2	CONCRETE, FORMWORK AND REINFORCEMENT	181		
3	METALWORK	184		
	Carried to Final Summary Section No. 3	R		
	SECTION SUMMARY			
	185			



SECTION NO. 4 PROVISIONAL SUMS



	11	NCDTSL01/2	2024
		Amount	
SECTION NO. 4			
SECTION NO. 4 PROVISIONAL SUMS			
FROVISIONAL SUMS			
NOTE: Tenderers are referred to the definition of attendance on n/s sub- contractors given in Clause B9 of the JBCC Preliminaries			
NOTE: All Provisional and Prime Cost Amounts are NET i.e: there is no cash discount			
NOTE:Under no circumstances may any Prime Cost - Provisional Amount, etc be extended at an amount lower than the amount given in the Bill			
NOTES:			
1. Where special attendance includes the provision of hoisting facilities for a Sub-Contractor then the Contractor shall:-			
*Ensure that the capacities of his hoisting equipment are sufficient to deal with the masses and quantities of the items to be hoisted,			
*Schedule the times of availability of the hoisting equipment for each Sub-Contractors,			
*Provide all necessary personnel to operate the hoisting equipment for each Sub-Contractor, all to enable the Sub-Contractor to execute the hoisting or lowering of his material, etc. Using the facilities provided by the Contractor			
Under no circumstances may any Provisional Amount, etc. be extended at an amount lower than the amount given in this Bill			
The Contractor must read each description throughout this bills of quantities in conjunction with and in the context of the obligations, requirements and specifications stated in the descriptions, the Model Preambles for Trades (2008 Edition) and any supplementary Preambles to the Model Preambles			
forming part of these Bills of Quantities			
No claim arising from brevity of description of items fully described in the said Model Preambles for Trades or Supplementary Preambles to Model Preambles will be granted			
All provisional sums cover supply of material and equipment and installation. provisional sums are nett and do not include builder's discount (excluding settlement discount) and Value Added Tax but the Tenderer may allow under "Profit" items any profit he considers necessary			
Electrical Installation			
Provide the amount of R 187 200.00 (One Hundred and Eighty Seven Thousand Two Hundred Rand Only) for Eletrical Installation and wiring for air conditioning units & fans as well as for adjustment of Mechanical engineering services to be used at the discretion of the principal agent and deducted in whole or in part if not required		407.000	
Profit.	Item	187.200	U
Allow for general attendance.	Item		
Carried To Section Summary	R -		
Section No. 4	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		
Bill No. 1			
Provisional Sums			
187			



			NCDTSL01/2024	4
			Amount	
	Alternative Energy Supply			
4	Provide the amount of R 167 440.00 (One Hundred and Sixty Seven Thousand Four Hundred and Forty Rand Only) for provision of an alternative energy supply.	Item	167.440 00	
5	Profit.	Item		
6	Allow for general attendance.	Item		
	ASBESTOS ROOF REMOVAL AND DISPOSAL			
	Asbestos Roof Removal and Disposal			
7	Provide the amount of R 185 120.00 (One Hundred and Eighty Five Thousand One Hundered and Twenty Rand Only) for appointment of a asbestos removal contractor, who shall remove and dispose of asbestos roofing and dispose at an approved asbestos disposal landfill	Item	185.120 00	
8	Profit.	Item		
9	Allow for general attendance.	Item		
	SECURITY GUARDROOM			
10	Provide the amount of R 78 000.00 (Seventy Eight Thousand Rand Only) for provision of a fibreglass wendy security guradroom	Item	78.000 00	
11	Add for Profit	Item	7 0.000	
12	Add for Attendance	Item		
	Carried To Section Summary Section No. 4 Bill No. 1 Provisional Sums	R		_



			Amount	2024
			Amount	
SECTION NO. 4				
PROVISIONAL SUMS				
SECTION SUMMARY		D		
		Page		
	Brought forward from page	187		
	Brought forward from page	188		
	Carried to Final Summary	R		
Section No. 4 SECTION SUMMARY				
CESTION COMMENT				
	189			





SECTION NO. 5 BUDGTARY ALLOWANCES



			NCDTSL01/2	2024
			Amount	
	SECTION NO. 5 BUDGTARY ALLOWANCES			
1	Thousand Rand Only) to be directed by the Director of Roads and Public	tem	156.000	00
	Carried to Final Summary Section No. 5 Bill No. 1 Provisional Sums	R		



	R & R AT COLESE	SERG WEIG	HBR	IDGE - Principal Con NCDTSL01/2	
Section No.	FINAL SUMMARY	Page		Amount	
1	PRELIMINARIES AND GENERAL	141			
2	BUILDING WORKS	173			
3	EXTERNAL WORKS[PROVISIONAL]	185			
4	PROVISIONAL SUMS	189			
5	BUDGTARY ALLOWANCES	191			
	SubTotal excluding Value Added Tax				
	ADD VAT @ 15%:				
	Carried to Tender		R		=
	FINIAL CLIMMADY				
	FINAL SUMMARY				
	192				



INDEX TO BILLS OF QUANTITIES

Bill No		Page No
	SECTION NO. 1: PRELIMINARIES AND GENERAL	116
	Meaning Of Terms 'Tender / Tenderer!	117
	Preliminaries	117
	Pricing Of Preliminaries	117
	Section A: Jbcc Principal Building Agreement	117
	A1.0 Definitions And Interpretation	117
	Objective And Preparation	118
	A2.0 Offer, Acceptance And Performance	118
	A3.0 Documents	118
	A4.0 Design Responsibility	119
	A5.0 Employer's Agents	119
	A6.0 Site Representative	119
	A7.0 Compliance With Regulations	119
	A8.0 Works Risk	119
	A9.0 Indemnities	119
	A10.0 Works Insurances	119
	A11.0 Liability Insurances	121
	A12.0 Effecting Insurances.	122
	A13.0 No Clause	122
	A14.0 Security	122
	Execution	124
	A15.0 Preparation For And Execution Of The Works	124
	A16.0 Access To The Works	124
	A17.0 Contract Instructions	124



A18.0 Setting Out Of The Works	125
A19.0 Assignment	125
A20.0 Nominated Subcontractors	125
A21.0 Selected Subcontractors	125
A22.0 Employer's Direct Contractors.	125
A23.0 Contractor's Domestic Subcontractors	125
Completion	125
A24.0 Practical Completion	125
A25.0 Works Completion	125
A26.0 Final Completion	125
A27.0 Latent Defects Liability Period	125
A28.0 Sectional Completion	125
A29.0 Revision Of Date For Practical Completion.	125
A30.0 Penalty For Non-completion	126
Payment	126
A31.0 Interim Payment To The Contractor.	126
A32.0 Adjustment To The Contract Value	127
A33.0 Recovery Of Expense And Loss	127
A34.0 Final Account And Final Payment	127
A35.0 Payment To Other Parties	127
Cancellation	127
A36.0 Cancellation By Employer - Contractor's Default	127
A37.0 Cancellation By Employer - Loss And Damage	128
A38.0 Cancellation By Contractor - Employer's Default	128
A39.0 Cancellation - Cessation Of The Works	128
Dispute	128



A40.0 Dispute Settlement	128
Substitute Provisions	129
A41.0 State Clauses	129
Contract Variables	129
A42.0 The Schedule (Dpw-04ec)	129
Section B: Jbcc Preliminaries	129
B1.0 Definitions And Interpretation	129
B2.0 Documents	129
B3.0 The Site	129
B4.0 Management Of Contract	130
B5.0 Samples, Shop Drawings And Manufacturers' Instructions	130
Temporary Works And Plant	130
B7.0 Temporary Services	130
Prime Cost Amounts	131
B9.0 Attendance On N/s Subcontractors	131
B10.0 Financial Aspects	131
B11.0 General	131
B1.0 Definitions And Interpretation	132
Schedule Of Variables	132
12.1 Pre-tender Information	132
12.2 Post-tender Information	134
Section C: Specific Preliminaries	135
C1 Contract Drawings	135
C2 General Preambles	135
C3 Trade Names	135
C4 Imported Materials And Equipment	136



	C5 Viewing The Site In Security Areas	136
	C6 Commencement Of Works In Security Areas	136
	C7 Entrance Permits To Security Areas	136
	C8 Security Check Of Personnel	136
	C9 Prohibition On Taking Of Photographs	136
	C10 Hiv/aids Awareness	137
	C10.1 Awareness Champion	137
	C10.2 Awareness Workshops.	137
	C10.3 Posters, Booklets, Videos, Etc	137
	C10.4 Access To Condoms	137
	C10.5 Monitoring	138
	C11 Occupational Health And Safety Act	138
	Epwp	139
	Carting Of Water For Construction	139
	Portfolio Of Evidence	139
	Electrical Installation & Other Subcontractor's Preliminaries	140
5	SECTION SUMMARY	141
5	SECTION NO. 2: BUILDING WORKS	142
1 <i>A</i>	ALTERATIONS [PROVISIONAL]	143
	Supplementary Preambles	143
	Remove Existing Work	145
	Doors	145
	Grilles, Gates, Etc.	145
	Floor Finishes	145
	Wall Finishes	146
	Ceilings	146



	Fittings	146
	Sanitary Fittings	146
	Sanitary Plumbing	147
	Mechanical Equipment	147
2 F	ROOF COVERINGS	149
	Profiled Metal Sheeting And Accessories	149
	Roof And Wall Insulation	149
3 C	CARPENTRY AND JOINERY	150
	Supplementary Preambles	150
	Roofs Etc	150
	Doors Etc	152
	Fittings	152
4 C	CEILINGS PARTITIONS AND ACCESS FLOORING	155
	Supplementary Preambles	155
	Nailed-up Ceilings	155
5 II	RONMONGERY	156
	Supplementary Preambles	156
	Hinges, Bolts, Etc	156
	Locks	156
	Handles	156
	Pinning Boards, Writing Boards, Projection Screens, Etc	157
	Bathroom Fittings	157
	Letters, Nameplates, Etc	157
	Sundries	157
6 N	METALWORK	159
	Supplementary Preambles	159



	Galvanised Mild Steel Gates, Screens, Etc	160
	Steel Roller Shutters Etc	160
7 T	ILING	162
	Supplementary Preambles	162
	Wall Tiling	162
	Floor Tiling	162
8 P	PLUMBING AND DRAINAGE	163
	Supplementary Preambles	163
	Rainwater Disposal	165
	Sanitary Fittings	165
	Waste Unions Etc	165
	Traps Etc	165
	Taps, Valves, Etc.	165
	Sanitary Plumbing	166
	Water Supplies	166
	Solar Water Heaters	167
	Fire Appliances Etc	167
9 0	GLAZING	169
	Supplementary Preambles	169
	Glazing To Steel With Putty	169
	Tops, Shelves, Doors, Mirrors, Etc	169
10 P	PAINTWORK	170
	Preparatory Work To Existing Work	170
	Paintwork To Existing Work	170
	On Floated Plaster	170
	Paintwork Etc To New Work	170



	On Plaster Board	170
	On Wood Surfaces	170
	On Metal Surfaces	171
	SECTION SUMMARY	173
	SECTION NO. 3: EXTERNAL WORKS[PROVISIONAL]	174
1	EARTHWORKS	175
	Supplementary Preambles	175
	Demolitions Etc	176
	Site Clearance Etc.	176
	Excavation Etc	176
	Filling Etc Other Than Bulk	177
	Soil Poisoning	177
2	CONCRETE, FORMWORK AND REINFORCEMENT	179
	Supplementary Preambles	179
	Unreinforced Concrete Cast On/in Formwork	180
3	METALWORK	182
	Supplementary Preambles	182
	Fencing	183
	SECTION SUMMARY	185
	SECTION NO. 4: PROVISIONAL SUMS	186
	Asbestos Roof Removal And Disposal	188
	Asbestos Roof Removal And Disposal	188
	Security Guardroom	188
	SECTION SUMMARY	189
	SECTION NO. 5: BUDGTARY ALLOWANCES	190
	Supplementary Preambles	191



Contintency (This Section Is Not Part On Bidders Document)	191
SECTION SUMMARY	192